


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 SW 1/4 NE 1/4	Section number 29	Township number T 27 S	Range number R 1 W
2. Distance and direction from nearest town or city: Street address of well location if in city:		3. Owner of well: O. E. Thompson R.R. or street: 611 Keith City, state, zip code: Wichita, Kansas 67209			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: 		6. Bore hole dia. 11 in. Completion date 1-22-77 Well depth 90 ft.	
5. Type and color of material		From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Topsoil		0	2	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Clay		2	10	9. Casing: Material styrene Height: Above ground 6' Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 90 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200	
Fine Sand		10	35	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gauge .06 Length 10' Set between 80 ft. and 90 ft. ft. and 1-1/8" Gravel pack? yes Size range of material 1-1/8"	
Medium Sand (dirty)		35	50	11. Static water level: 30 ft. below land surface Date 1-22-77	
Fine Sand with clay balls		50	75	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
Medium Sand		75	90	13. Water sample submitted: mo./day/yr. ☐ Yes ☐ No Date	
				14. Well head completion: ☒ Pitless adapter 12 Inches above grade	
				15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
				16. Nearest source of possible contamination: Septic ft. 70 Direction West Type tank Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: Not installed Manufacturer's name Sta-Rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 65 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 1-26-77 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5