


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NE 1/4 NW 1/4 NE 1/4	Section number 29	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: 444 Herschel Street address of well location if in city: Wichita, Kansas			3. Owner of well: Larry Bennett R.R. or street: 803 North Sheridan #203 City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 5-11-76 Well depth 110 ft.	
Topsoil			0	2	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Sandy Clay			2	18	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand with Clay Streaks			18	32	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 110 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200	
Fine Sand			32	50	10. Screen: Manufacturer's name Sunflower Plastic Type Styrene Dia. 5" Slot/gauge .06 Length 10' Set between 100 ft. and 110 ft. ft. and 110 ft. Gravel pack? yes Size range of material 1/4-1/8"	
Grey Clay			50	71	11. Static water level: ☐ mo./day/yr. 29 ft. below land surface Date 5-11-76	
Fine Sand			71	90	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
Coarse Sand			90	110	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐	
					14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft. OK	
					16. Nearest source of possible contamination: Septic Tank ft. 65 Direction West Type Tank Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Sta-Rite Model number 20P4E02 HP 1 Volts 230 Length of drop pipe 50 ft. capacity 25 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Flat Ground Well is in the garage.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. Address Wichita, Kansas Signed M. Arnold Date 5-6-77 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5