


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NE NW SE NE

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 NE 1/4	Section number 29	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: 500 So. Westfield			3. Owner of well: Dora Barker R.R. or street: 500 South Westfield City, state, zip code: Wichita, Kansas 67209			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole: Bore hole dia. 11 in. Completion date 5-5-77 Well depth 120	
Topsoil			0	3	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Clay			3	25	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand			25	45	9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☒ PVC ☐ Weight 81 lbs./ft. Dia. 5 in. to 120 ft. depth Wall Thickness: inches or Dia. 5 in. to 120 ft. depth Page No. 200	
Clay			45	50	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gauge 0.06 Length 15' Set between 105 ft. and 120 ft. Gravel pack? yes Size range of material 1/4-1/8"	
Fine Sand			50	98	11. Static water level: 35 ft. below land surface Date 5-5-77	
Clay			98	101	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.	
Medium Sand			101	120	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☐ No Date ____	
					14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes 1 to 2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
					16. Nearest source of possible contamination: Septic ft. 50 Direction East Type Tank Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Jacuzzi Model number N/A HP 1 Volts 230 Length of drop pipe 55 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			(Use a second sheet if needed)			
18. Elevation:		19. Remarks: Installed customer pump.				
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. ____ Address ____ Signed M. Arnold Date 6-30-77 Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5