

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4NW 1/4 SW 1/4	Section number 29	Township number T 27 S R 1W E/W	Range number
2. Distance and direction from nearest town or city: Street address of well location if in city: 714 S. Maize Ct. Wichita, Kansas			3. Owner of well: Harold Keys Construction P.O.Box 9271 Wichita, Kansas R.R. or street: City, state, zip code:			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 6. Bore hole dia. 11 in. Completion date 11-30-77 Well depth 140 ft. 7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material styrene Height: Above or below/ Threaded ☐ Welded ☒ 81 Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dio. 5 in. to 140 ft. depth Wall Thickness: inches or Dio. ☐ in. to ☐ ft. depth gage No. 200			
5. Type and color of material			From	To	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dio. 5" Slot/gage 4/16 Length 10' Set between 130 ft. and 140 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 1/2-1/8"	
Topsoil			0	3	11. Static water level: 26 ft. below land surface Date 11-30-77	
Sandy Clay (Brown)			3	15	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
Fine Sand			15	25	13. Water sample submitted: mo./day/yr. Yes No Date	
Medium Sand			25	45	14. Well head completion: ☒ Pitless adapter 12 inches above grade	
Clay (Grey)			45	92	15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
Fine Sand			92	108	16. Nearest source of possible contamination: Septic ft. 70 Direction East Type Tank Well disinfected upon completion? ☒ Yes ☐ No	
Medium Sand			108	126	17. Pump: Not installed Manufacturer's name Sta-Rite Model number 20P4D02-HP 3/4 Volts 230 Length of drop pipe 50 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. Address Signed M. Arnold Date 12-12-77 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5