


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Sedgwick</u>	Fraction <u>1/4 NW 1/4 NE 1/4</u>	Section number <u>29</u>	Township number <u>T 27 S</u>	Range number <u>R 1W E/W</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>311 Mamie Wichita, Kansas</u>			3. Owner of well: <u>R.W. Brunner</u> R.R. or street: <u>311 Mamie</u> City, state, zip code: <u>Wichita, Kansas</u>		
4. Locate with "X" in section below: N Sketch map: 			6. Bore hole dia. <u>11</u> in. Completion date _____ Well depth <u>127</u> ft. <u>7-29-77</u>		
			7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material <u>Styrene</u> Height: Above or below _____ Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight _____ lbs./ft. Dia. <u>5</u> in. to <u>127</u> ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth Gauge No. <u>.200</u>		
5. Type and color of material			From	To	
<u>Topsoil</u>			<u>0</u>	<u>3</u>	10. Screen: Manufacturer's name <u>Sunflower Plastic</u>
<u>Clay</u>			<u>3</u>	<u>16</u>	Type <u>Styrene</u> Dia. <u>5"</u>
<u>Medium Sand</u>			<u>16</u>	<u>31</u>	Slot/gauge <u>.06</u> Length <u>10'</u>
<u>Medium Sand mixed with Clay streaks</u>			<u>31</u>	<u>46</u>	Set between <u>117</u> ft. and <u>127</u> ft.
<u>Medium Sand</u>			<u>46</u>	<u>59</u>	_____ ft. and _____ ft.
<u>Coarse Sand</u>			<u>59</u>	<u>66</u>	Gravel pack? <u>yes</u> Size range of material <u>1/2-1/8"</u>
<u>Clay</u>			<u>66</u>	<u>87</u>	11. Static water level: _____ mo./day/yr. <u>38</u> ft. below land surface Date <u>7-29-77</u>
<u>Fine Sand to Medium</u>			<u>87</u>	<u>106</u>	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m.
<u>Medium Coarse Sand</u>			<u>106</u>	<u>115</u>	Estimated maximum yield _____ g.p.m.
<u>Coarse Sand mixed with Fine Gravel</u>			<u>115</u>	<u>127</u>	13. Water sample submitted: _____ mo./day/yr. Yes _____ No _____ Date _____
					14. Well head completion: <u>Well Seal</u> _____ Pitless adapter <u>12</u> inches above grade
					15. Well grouted? <u>yes</u> <u>to 2 fine sand mix.</u> With: _____ Neat cement _____ Bentonite ☒ Concrete _____ Depth: From <u>40"</u> ft. to <u>14</u> ft.
					16. Nearest source of possible contamination: <u>Septic</u> ft. <u>90</u> Direction <u>West</u> Type <u>Tank</u> Well disinfected upon completion? ☒ Yes _____ No _____
					17. Pump: _____ Not installed Manufacturer's name <u>Pioneer</u> Model number <u>B70</u> HP <u>3</u> Volts <u>230</u> Length of drop pipe <u>50</u> ft. capacity <u>60</u> g.p.m. Type: ☒ Submersible _____ Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other _____
18. Elevation:			19. Remarks: <u>Flat Ground</u> <u>Well is to be used for Sprinkler system.</u>		
Topography: ____ Hill ____ Slope ____ Upland ____ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Harp Well & Pump</u> <u>236</u> Business name License No. Address <u>Wichita, Kansas</u> Signed <u>[Signature]</u> Date <u>8-9-77</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5