


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NE SW NW NW

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 NW 1/4	Section number 29	Township number T 27 S R 1W E/W	Range number
2. Distance and direction from nearest town or city: Street address of well location if in city: 433 Wetmore Drive Wichita, Kansas			3. Owner of well: Geo. Bostrom R.R. or street: 433 Wetmore Drive City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date Well depth 140 ft. 4-22-77	
Topsoil			0	4	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Brown Clay			4	16	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand			16	19	9. Casing: Material Styrene Height: Above or Below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 140 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 1200	
Brown Clay			19	30	10. Screen: Manufacturer's name Sunflower Plastic	
Fine Sand			30	34	Type Styrene Dia. 5" Slot size .06 Length 20' Set between 120 ft. and 140 ft. ft. and ☐ ft. Gravel pack ☒ yes Size range of material 1/2-1/8"	
Lt. Brown Clay			34	45	11. Static water level: ☐ mo./day/yr. 30 ft. below land surface Date 4-22-77	
Fine Sand			45	95	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
Lt. Brown Clay			95	100	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date	
Fine Sand			100	105	14. Well head completion: ☒ Pitless adapter 12 Inches above grade	
Lt. Brown Clay			105	115	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
Medium Sand			115	140	16. Nearest source of possible contamination Sewer ft. 60 Direction South Type Lines Well disinfected upon completion? ☒ Yes ☐ No	
(Use a second sheet if needed)					17. Pump: ☐ Not installed Manufacturer's name Jacuzzi Model number 7S4C HP 3/4 Volts 220 Length of drop pipe 50 ft. capacity ☐ g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. Address Wichita, Kansas Signed M. Arnold Date 5-18-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5