


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NW 1/4 NE 1/4 SW 1/4	Section number 29	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: 718 Maize Court, Wichita, Kansas Street address of well location if in city:			3. Owner of well: Harold Keys Construction R.R. or street: P.O. Box 9271 City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: 			Sketch map:		6. Bore hole dia. 11 in. Completion date _____ Well depth 150 ft. 10-2-78	
5. Type and color of material			From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Topsoil			0	2	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Sandy clay			2	15	9. Casing: Material Styrene Height: Above or below _____ Threaded _____ Welded g1 Surface 12 in. RMP ☒ PVC _____ Weight _____ lbs./ft. Dia. 5 in. to 150 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. .200	
Clay			15	25	10. Screen: Manufacturer's name _____ Sunflower plastic Type styrene Dia. 5" Slot/gage 06 Length 20' Set between 130 ft. and 150 ft. _____ ft. and _____ ft. Gravel pack? yes Size range of material 1/4-1/8"	
Sandy clay			25	27	11. Static water level: _____ mo./day/yr. 21 ft. below land surface Date 10-2-78	
Fine to Medium sand			27	45	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
Medium sand			45	51	13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____	
Clay			51	76	14. Well head completion: ☒ Pitless adapter 12 inches above grade	
Fine sand			76	84	15. Well grouted? yes 1-2 fine sand mix With: _____ Neat cement _____ Bentonite ☒ Concrete Depth: From 40 ft. to 14 ft.	
Clay			84	105	16. Nearest source of possible contamination: ft. 70 Direction South Type Septic Well disinfected upon completion? ☒ Yes tank No	
Fine to Medium sand			105	120	17. Pump: _____ Not installed Manufacturer's name Jacuzzi Model number 7S4C HP 3/4 Volts 230 Length of drop pipe 45 ft. capacity 20 g.p.m. Type: ☒ Submersible _____ Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other	
Medium sand			120	132	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name _____ License No. _____ Address Wichita, Kansas 67209 Signed Dr. Arnold Date 12-12-78 Authorized representative	
Medium to coarse sand			132	150		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: Flat ground				
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5