

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Sedgewick</u> Fraction <u>SW 1/4 NW 1/4 SE 1/4</u> Section number <u>29</u> Township number <u>T 27 S</u> Range number <u>R 1 E</u>																									
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1216 Scoville Wichita KS</u>																									
3. Owner of well: <u>Tom Little</u> R.R. or street: <u>7333 Freeman</u> City, state, zip code: <u>Wichita KS 67212</u>																									
4. Locate with "X" in section below: Sketch map: <u>well in basement house</u>																									
6. Bore hole dia. <u>11</u> in. Completion date <u>2/10/79</u> Well depth <u>95</u> ft.																									
7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																									
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																									
9. Casing: <u>Square</u> Height: <u>0</u> Above or below Threaded ☒ Welded ☒ Surface <u>13</u> in. RMP <u>5</u> ☒ PVC Weight <u>1.50</u> lbs./ft. Dia. <u>5</u> in. to <u>25</u> ft. depth Wall thickness: inches or Dia. <u>25</u> in. to <u>25</u> ft. depth gage No. <u>200</u>																									
5. Type and color of material																									
<table border="1"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td>Top soil</td> <td>0</td> <td>2</td> </tr> <tr> <td>red clay</td> <td>2</td> <td>34</td> </tr> <tr> <td>fine sand</td> <td>34</td> <td>56</td> </tr> <tr> <td>ored clay</td> <td>56</td> <td>64</td> </tr> <tr> <td>fine sand</td> <td>64</td> <td>79</td> </tr> <tr> <td>gray clay</td> <td>79</td> <td>80</td> </tr> <tr> <td>med to coarse sand</td> <td>80</td> <td>95</td> </tr> </tbody> </table>			From	To	Top soil	0	2	red clay	2	34	fine sand	34	56	ored clay	56	64	fine sand	64	79	gray clay	79	80	med to coarse sand	80	95
	From	To																							
Top soil	0	2																							
red clay	2	34																							
fine sand	34	56																							
ored clay	56	64																							
fine sand	64	79																							
gray clay	79	80																							
med to coarse sand	80	95																							
10. Screen: Manufacturer's name <u>Sunflower</u> Type <u>200</u> Dia. <u>5</u> in. Slot gauge <u>1/16</u> Length <u>6</u> ft. Set between <u>80</u> ft. and <u>90</u> ft. Gravel pack? <u>yes</u> Range of material <u>3/8</u> in. to <u>3/4</u> in. Static water level: <u>30</u> ft. below land surface Date <u>2/10/79</u> Pumping level below land surfaces: <u>34</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. <u>34</u> ft. after <u>1</u> hrs. pumping <u>15</u> g.p.m. Estimated maximum yield <u>35</u> g.p.m.																									
13. Water sample submitted: ☒ Yes ☐ No Date <u>2/10/79</u>																									
14. Well head completion: <u>12</u> Pitless adapter <u>12</u> Inches above grade																									
15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>6</u> ft. to <u>16</u> ft.																									
16. Nearest source of possible contamination: <u>100</u> ft. Direction <u>E</u> Type <u>Septic</u> Well disinfected upon completion? ☒ Yes ☐ No																									
17. Pump: ☒ Not installed Manufacturer's name <u>Wenger</u> Model number <u>318</u> HP <u>1/2</u> Volts <u>115</u> Length of drop pipe <u>25</u> ft. capacity <u>15</u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																									
(Use a second sheet if needed)																									
18. Elevation: Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: <u>27 L-29 SW 1/4 SE 1/4</u>																								
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Business name <u>Wenger</u> License No. <u>318</u> Address <u>Wichita KS</u> Signature <u>Wenger</u> Date <u>2/10/79</u> Authorized representative																									

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5