


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction 1/4 NE 1/4 NW 1/4	Section number 30	Township number T 27 S R 1 E W	Range number 1
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: HAROLD REYS CONSTR. R.R. or street: 301 SHEPHERD City, state, zip code: WICHITA, KANSAS			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 10-2-76 Well depth 140 ft.	
TOPSOIL			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
SANDY CLAY			2	17	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
FINE SAND WITH CLAY BALLS			17	30	9. Casing: Material STYRENE Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 140 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 1200	
FINE SAND			30	60	10. Screen: Manufacturer's name SUNFLOWER PLASTIC Type STYRENE Dia. 5" Slot gauze .06 Length 20' Set between 120 ft. and 140 ft. ft. and 140 ft.	
GRAY CLAY			60	90	Gravel pack? YES Size range of material 1/4-1/8"	
FINE SAND WITH CLAY STREAKS			90	108	11. Static water level: 25 ft. below land surface Date 10-2-76 mo./day/yr.	
FINE SAND			108	120	12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
COARSE SAND			120	140	13. Water sample submitted: ☐ Yes ☐ No Date ☐ mo./day/yr.	
					14. Well head completion: 12 CAPPED Pitless adapter ☐ 12 inches above grade	
					15. Well grouted? YES With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" to 14 ft.	
					16. Nearest source of possible contamination: SEWER ft. 65 Direction SO Type LINE Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks: FLAT GROUND WELL TO BE IN BASEMENT. PUMP TO BE INSTALLED AT A LATER DATE.			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. HARP WELL+Pump 236 Business name ☐ License No. ☐ Address WICHITA, KANSAS Signed M. Arnold Date 12-20-76 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5