

USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 SE 1/4 SE 1/4	Section number 30	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 1302 Lark Lane Wichita, Kansas			3. Owner of well: Don Love R.R. or street: 1302 Lark Lane City, state, zip code: Wichita, Kansas 67209		
4. Locate with "X" in section below: N Sketch map: W E S 1 Mile			6. Bore hole dia. 11 in. Completion date 10-6-77 Well depth 135 ft.		
			7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 8 lbs./ft. Dia. 5 in. to 135 ft. depth Wall Thickness: inches or Dia. 5 in. to 135 ft. depth gage No. 200		
5. Type and color of material			From	To	10. Screen: Manufacturer's name Sunflower Plastic
					Type styrene Dia. 5 "
Topsoil			0	3	Slot/gauge 1/4 .06 Length 10 '
Clay			3	10	Set between 125 ft. and 135 ft.
Fine Sand			10	18	ft. and 135 ft.
Medium Sand (dirty)			18	40	Gravel pack? yes Size range of material 1/2-1/8 "
Clay			40	85	11. Static water level: 25 ft. below land surface Date 10-6-77
Fine Sand			85	97	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
Medium Sand			97	135	13. Water sample submitted: Yes No Date 10-6-77
					14. Well head completion: ☒ Pitless adapter 12 inches above grade
					15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40 ft. to 14 ft.
					16. Nearest source of possible contamination: Septic ft. 75 Direction North Type Tank Well disinfected upon completion? ☒ Yes No
					17. Pump: Not installed Manufacturer's name Hydraulic Products Model number DH8 HP 3/4 Volts 230 Length of drop pipe 50 ft. capacity 20 g.p.m.
					Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business Wichita, Kansas License No. Address m. Arnold Signed m. Arnold Date 10-6-77 Authorized representative
18. Elevation:			19. Remarks:		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5