


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

Sent to BWS
12/17/78

1. Location of well:	County Sedgwick	Fraction SE 1/4 SW 1/4 NW 1/4	Section number 31	Township number T 27 S R 1	Range number 1
2. Distance and direction from nearest town or city: 2 mi. West of Wichita Airport Street address of well location, if in city: East of 119th West & So. of 4554			3. Owner of well: City of Goddard R.R. or street: Goddard, Kansas City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map:  Well No. 6 (TH 1-78)		6. Bore hole dia. 38" in. Completion date 11/27/78 Well depth 140 ft.	
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Top soil		0	3	8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Hard clay - lt. brown		3	9	9. Casing: Material S.St. Height: Above surface Threaded ☐ Welded ☐ Surface 36 in. RMP ☐ PVC ☐ Weight 43.77 lbs./ft. Dia 12 in. 78 ft. depth Wall Thickness: inches or Dia 12 in. to 130 ft. depth gage No. .330"	
Sandy clay w/brown gravel		9	25	10. Screen: Manufacturer's name Mustang Type S.St. W.W. Dia. 12" Slot/gauze .080 Length 40' Set between 78 ft. and 108 ft. 130 ft. and 140 ft. Gravel pack? yes Size range of material #8	
Blue & gray clay mixed w/gravel		25	30	11. Static water level: 25 ft. below land surface Date 11/16/78	
Dk. blue clay w/blue sand		30	40	12. Pumping level below land surfaces: 54 ft. after 8 hrs. pumping 500 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 1000 g.p.m.	
Brown sandy clay		40	50	13. Water sample submitted: Yes ☒ No ☐ Date	
Dk blue sand & clay		50	55	14. Well head completion: ☒ Pitless adapter 36 Inches above grade	
Blue shale		55	65	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 20 ft. to 5 ft. Per State Approved Plan	
Brown sand		65	72	16. Nearest source of possible contamination: ft. 400 Direction SW Type Farm Well disinfected upon completion? ☒ Yes ☐ No	
Brown clay		72	74	17. Pump: ☐ Not installed Manufacturer's name Layne & Bowler Model number BPRHC HP 60 Volts 460 Length of drop pipe 80 ft. capacity 400 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Brown sand		74	80	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. Address 1244 N. 1st St. Signed [Signature] Date 12/17/78 Authorized representative	
Brown sand		80	85		
Brown sand		85	96		
Brown clay		96	98		
Brown sand		98	106		
Hard gray shale		106	110		
Blue shale		110	118		
Gray shale		118	130		
Brown sand		130	135		
Brown sand		135	139		
Gray shale		139	140		
18. Elevation: 139 Remarks:					
19. Remarks:					
Hill					
Slope					
☒ Upland					
Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5