

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

sent to BWS

12/7/78

1. Location of well:		County Sedgwick	Fraction SW 1/4 SE 1/4 NW 1/4	Section number 31	Township number T 27 S R 1	Range number 1
2. Distance and direction from nearest town or city: 2 mi West of Wichita Airport Street address of well location if in city: East of 119th West of South 11554				3. Owner of well: City of Goddard, Kansas R.R. or street: Goddard, Kansas City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile Sketch map: Well No. 7 (TH 2-78)				6. Bore hole dia. 38 in. Completion date Well depth 135 ft. 11/27/78		
5. Type and color of material				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil				9. Casing: Material STL Height: Above ground Threaded ☐ Welded ☐ Surface 36 in. RMP ☐ PVC ☐ Weight 43.77 lbs./ft. Dia. 12 in. to 10 1/2 ft. depth Wall thickness: inches pr Dia. 12 in. to 9 1/2 ft. depth gauge No. 330		
				10. Screen: Manufacturer's name Mustang Wine Wrap Type St. Steel Dia. 12" Slot/gauze .080" Length 40' Set between 64 ft. and 74 ft. 95 to 120 ft. and 130 to 135 ft. Gravel pack? Yes Size range of material #8		
Dark brown clay				11. Static water level: 24 ft. below land surface Date 11-30-78		
XXXXXX Brown sand				12. Pumping level below land surfaces: 55 ft. after 5 hrs. pumping 503 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 1000 g.p.m.		
Gray clay				13. Water sample submitted: Yes ☒ No ☐ Date		
Gray clay & blue shale				14. Well head completion: ☒ Pitless adapter 36 inches above grade		
Blue shale				15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth from 20 ft. to 5 ft. per state		
Heavy gravel & sand				16. Nearest source of possible contamination: ft. 1300 Direction SW Type Farm Well disinfected upon completion? ☒ Yes ☐ No		
Blue shale				17. Pump: Manufacturer's name Layne & Bowler Model number BPRNC HP 60 Volts 460 Length of drop pipe 80 ft. capacity 400 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Sand				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. Address Wichita, Kansas Signed [Signature] Date 12/4/78 Authorized representative		
Hard clay						
Sand & Gravel						
Shale - gray						
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5