

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SE 1/4 NW 1/4 SE 1/4	Section number 32	Township number T 27 S R 1	Range number 1
2. Distance and direction from nearest town or city: Street address of well location if in city: 9220 West Pawnee				3. Owner of well: Board of Park Commissioners R.R. or street: 11th Floor - City Bldg. City, state, zip code: Wichita, Kansas 67202		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>34</u> in. Completion date <u>Aug. 1, 1978</u> Well depth <u>116</u> ft.		
		Well No. 1 (TH 1-77)		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
5. Type and color of material		From	To	9. Casing: Material <u>Steel</u> Height: Above <u>surface</u> Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>45</u> lbs./ft. Dia. <u>12</u> in. to <u>86</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>0.330"</u>		
Top soil		0	2	10. Screen: Manufacturer's name <u>Layne</u> Type <u>Shutter</u> Dia. <u>12"</u> Slot/gauze <u>0.105"</u> Length <u>30'</u> Set between <u>70'</u> ft. and <u>80'</u> ft. <u>96</u> ft. and <u>116</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8-3/8</u>		
Brown silt		2	15	11. Static water level: <u>28</u> ft. below land surface Date <u>4/12/78</u> mo./day/yr.		
Fine to med. sand & gravel		15	34	12. Pumping level below land surfaces: <u>40</u> ft. after <u>4</u> hrs. pumping <u>325</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>900</u> g.p.m.		
Gray clay and sand streaks		34	53	13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No <u> </u> Date <u> </u>		
Fine to med. sand & gravel		53	60	14. Well head completion: <u> </u> Pitless adapter <u>30</u> inches above grade		
Brown clay		60	63	15. Well grouted? <u>yes</u> With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
Fine to med. sand & gravel & clay		63	80	16. Nearest source of possible contamination: ft. <u> </u> Direction <u> </u> Type <u>None</u> Well disinfected upon completion? ☒ Yes <u> </u> No		
Brown & blue clay		80	95	17. Pump: Manufacturer's name <u>Layne</u> Not installed Model number <u>8RKHC</u> HP <u>40</u> Volts <u> </u> Length of drop pipe <u>100</u> ft. capacity <u>300</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other		
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name <u>Wichita, Kansas</u> License No. <u> </u> Address <u> </u> Signed <u>OR Soder</u> Date <u>8-8-78</u> Authorized representative		
18. Elevation: <u>1360±</u> Topography: <u> </u> Hill <u> </u> Slope ☒ Upland <u> </u> Valley		19. Remarks:				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5