


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction 1/4 NE 1/4 NE 1/4	Section number 33	Township number T 27 S R	Range number 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 7117 W. Harry St. Wichita, Kansas			3. Owner of well: U.S. Postal Service R.R. or street: 7117 W. Harry St. City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 		6. Bore hole dia. 14 in. Completion date _____ Well depth 65 ft. 5-17-78	
			7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other	
			9. Casing: Material PVC Height: Above of 464 Threaded _____ Welded _____ Surface 24 in. RMP _____ PVC ☒ Weight 5.47 lbs./ft. Dia. 8 in. to 65 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. .332			
5. Type and color of material			From	To	10. Screen: Manufacturer's name PVC NSF approved 160 PSI	
Topsoil			0	2	Type PVC 160 PSI Dia. 8"	
Brown Clay			2	14	Slot/gauge .06 Length 20'	
Fine Sand			14	21	Set between 45 ft. and 65 ft. _____ ft. and _____ ft.	
Gray Clay			21	23	Gravel pack? yes Size range of material 1/4-1/8"	
Fine Sand			23	40	11. Static water level: _____ mo./day/yr. 20 ft. below land surface Date 5-17-78	
Medium Sand			40	63	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
Gray Clay			63	65	13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____	
					14. Well head completion: capped ☐ Pitless adapter 24 inches above grade	
					15. Well grouted? yes 1-2 Fine Sand Mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
					16. Nearest source of possible contamination: City _____ ft. 100 Direction No. Type Sewer Line Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. _____ Address Wichita, Kansas 67209 Signed M. Arnold Date 5-30-78 Authorized representative	
18. Elevation:			19. Remarks: Flat Ground Pump not installed at this time. Well to be used for Sprinkler System for lawn.			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5