

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 SE 1/4	Section number 34	Township number T 27 S	Range number R 1 W
2. Distance and direction from nearest town or city: Street address of well location if in city: 2021 S. Eisenhower (SE Corner of Bldg Site)				3. Owner of well: R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile				3. Owner of well: Aviation Education Center Wichita, Kansas		
Sketch map: Well No. 2 (Disposal Well)				6. Bore hole dia. 30 in. Completion date 9/6/78 Well depth 50 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☒ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material Stl Height: Above 18 in. Threaded ☐ Welded ☒ Surface 18 in. RMP ☐ PVC ☐ Weight 40.48 lbs./ft. Dia 10 in. to 40 ft. depth Wall Thickness: inches .365 Dia. ☐ in. to ☐ ft. depth Gauge No. ☐		
5. Type and color of material		From	To	10. Screen: Manufacturer's name Layne		
Brown clay		0	10	Type St. Steel Dia. 10"		
Brown silty clay		10	15	Slot/gauze .155 Length 10'		
Med. to coarse sand & gravel		15	25	Set between 40 ft. and 50 ft.		
Brown clay		25	30	Gravel pack? yes Size range of material 1/4 X 1/2		
Blue clay		30	40	11. Static water level: 11 ft. below land surface Date 9/6/78		
Med. to coarse sand & gravel		40	50	12. Pumping level below land surfaces: No Test		
Tan clay		50		Estimated maximum yield ☐ g.p.m.		
				13. Water sample submitted: ☐ Yes ☒ No Date ☐		
				14. Well head completion: 18 inches above grade		
				15. Well grouted? yes		
				With: ☐ Neat cement ☐ Bentonite ☒ Concrete		
				Depth: From 0 ft. to 20 ft.		
				16. Nearest source of possible contamination: Bldg Sewer Line		
				ft. 100' Direction NW Type Sewer Line		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed		
				Manufacturer's name ☐		
				Model number ☐ HP ☐ Volts ☐		
				Length of drop pipe ☐ ft. capacity ☐ g.p.m.		
				Type: ☐ Submersible ☐ Turbine		
				☐ Jet ☐ Reciprocating		
				☐ Centrifugal ☐ Other		
18. Elevation:		20. Water well contractor's certification:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. ☐ Address ☐ Signed [Signature] Date 10/12/78 Authorized representative				
19. Remarks:						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5