

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 SE 1/4	Section number 34	Township number T 27 S	Range number R 1 W
2. Distance and direction from nearest town or city: Street address of well location if in city: 2021 S. Eisenhower			3. Owner of well: Aviation Education Center R.R. or street: Wichita City, state, zip code: Kansas			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: No. 1 (Supply Well)		6. Bore hole dia. 34 in. Completion date 9/8/78 Well depth 76 ft.	
5. Type and color of material			From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Top soil			0	2	8. Use: ☒ Domestic ☐ Public supply ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Brown clay			2	11	9. Casing: Material STL Height: Above 30 in. Threaded ☐ Welded ☒ Surface 30 in. RMP ☐ PVC ☐ Weight 40.48 lbs./ft. Dia. 10 in. to 66 ft. depth Wall Thickness: inches or Dia. 10 in. to 66 ft. depth gage No. 365	
Fine to med. sand & gravel			11	15	10. Screen: Manufacturer's name Layne Type St. Steel Dia. 10" Slot/gauze 105 Length 10' Set between 66 ft. and 76 ft. Gravel pack? yes Size range of material 1/8 x 1/2	
Gray-brown clay			15	19	11. Static water level: 15 ft. below land surface Date 9/8/78	
Med. to coarse sand & gravel			19	47	12. Pumping level below land surfaces: 18 ft. after 3 hrs. pumping 150 g.p.m. ft. after 3 hrs. pumping 150 g.p.m. Estimated maximum yield 500 g.p.m.	
Tan clay			47	51	13. Water sample submitted: Yes ☒ No ☐ Date 9/8/78	
Fine to med. sand & gravel & tan clay			51	55	14. Well head completion: ☐ Pitless adapter 30 inches above grade	
Fine to med. sand & gravel			55	60	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 20 ft.	
Tan clay			60	66	16. Nearest source of possible contamination: Bldg. ft. 504 Direction South Type Sewer Line Well disinfected upon completion? ☒ Yes ☐ No	
Med. to coarse sand & gravel			66	78	17. Pump: ☐ Not installed Manufacturer's name Layne & Bowler Inc. Model number BDRLC HP 10 Volts 460 Length of drop pipe 50 ft. capacity 135 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. 102 Address 1100 Bank Date 10/12/78 Signed Authorized representative	
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5