

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: 076 PRATT ; NE 1/4 NE 1/4 SE 1/4 ; 6 ; T 27 S ; R 13 W

Distance and direction from nearest town or city street address of well if located within city?
 1 1/2 W. OF IUKA, KS.

2 WATER WELL OWNER: LILLEQVIST, LUCKY 99
 RR#, St. Address, Box #: 618 SUNRISE Board of Agriculture, Division of Water Resources
 City, State, ZIP code : PRATT, KS 67124- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 131 ELEVATION:
 Depth(s) Groundwater Encountered 1. 59 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 59 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 131 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 112 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 112 ft. to 131 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 131 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 09 FEEDYARD
 Direction from well? SE How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	38	TAN CLAY			
38	65	05 SAND			
65	81	05 SAND AND 17 GRAVEL			
81	94	TAN CLAY			
94	105	05 SAND AND CLAY			
105	128	05 SAND AND 17 GRAVEL			
128	131	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 10/8 /91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11/02/91 under the business name of CARL MAYSE WATER WELL SVC by (signature) Carl Mayse