

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction SW 1/4 SW 1/4 SW 1/4	Section number 24	Township number T 27 S	Range number R 13 W E/W
2. Distance and direction from nearest town or city: 1 N & 2 E of			3. Owner of well: EDWIN MCGUIRE			
Street address of well location if in city: Pratt			R.R. or street: City, state, zip code: Pratt, Ks			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 10 in. Completion date 22 Apr 78 Well depth 90 ft.		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Soil		0	2	9. Casing: Material <input type="checkbox"/> Height Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 5 in. to 70 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 1258		
Sand, fine		2	8	10. Screen: Manufacturer's name perkins Type Saw slot Dia. 5 Slot/gauze 1/4 Length 20' Set between 70 ft. and 90 ft. ft. and <input type="checkbox"/> ft.		
Clay, tan, sandy		8	15	Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/4 x 1/4		
Sand, fine		15	30	11. Static water level: <input type="checkbox"/> mo./day/yr. 69.5 ft. below land surface Date 22 Apr 78		
Sand, fine to coarse and gravel		30	42	12. Pumping level below land surfaces: <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 40 g.p.m.		
Clay, tan and gray		42	56	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
Clay, tan, sandy		56	68	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 12 inches above grade		
Sand, fine to coarse		68	70	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 4 ft. to 14 ft.		
Sand, med. fine to coarse and fine to med. gravel		70	105	16. Nearest source of possible contamination: ft. 70 Direction SW Type Septic Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name STA RITE Model number 20 HP 3/4 Volts 230 Length of drop pipe 80 ft. capacity 15 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Central Well & Pump Svc. 325 Business name License No. Address 121 S. Taylor Pratt, Ks. Signed Johnamich Date 24 July 78 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		4'x4'x4" Slab poured below pit Adapter				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5