

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number						
County: PRATT		SW 1/4 SW 1/4 NW 1/4	19	T 27 S	R 14 EW						
Distance and direction from nearest town or city street address of well if located within city? 4 1/2 N OF CULLISON, KS											
2 WATER WELL OWNER: Texas Energies											
RR#, St. Address, Box # : Box 947			Board of Agriculture, Division of Water Resources								
City, State, ZIP Code : Pratt, Kansas 67124			Application Number:								
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 90 ft. ELEVATION:									
N 1 Mile W E S <table border="1" style="margin: auto; text-align: center;"><tr><td>NW</td><td>NE</td></tr><tr><td>X</td><td></td></tr><tr><td>SW</td><td>SE</td></tr></table>		NW	NE	X		SW	SE	Depth(s) Groundwater Encountered 1. 75 ft. 2. ft. 3. ft.			
		NW	NE								
		X									
		SW	SE								
		WELL'S STATIC WATER LEVEL 66 ft. below land surface measured on mo/day/yr MAY 27 81									
Pump test data: Well water was ft. after hours pumping gpm											
Est. Yield 50 gpm: Well water was ft. after hours pumping gpm											
Bore Hole Diameter 10 in. to 90 ft., and in. to ft.											
WELL WATER TO BE USED AS:											
5 Public water supply 8 Air conditioning 11 Injection well											
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)											
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well											
Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted											
Water Well Disinfected? Yes X No											
5 TYPE OF BLANK CASING USED:											
1 Steel 3 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped											
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded											
7 Fiberglass Threaded											
Blank casing diameter 5 in. to 75 ft., Dia in. to ft., Dia in. to ft.											
Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. 214											
TYPE OF SCREEN OR PERFORATION MATERIAL:											
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement											
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)											
12 None used (open hole)											
SCREEN OR PERFORATION OPENINGS ARE:											
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)											
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes											
7 Torch cut 10 Other (specify)											
SCREEN-PERFORATED INTERVALS: From 75 ft. to 90 ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
GRAVEL PACK INTERVALS: From ft. to ft., From ft. to ft.											
From 10 ft. to 90 ft., From ft. to ft.											
6 GROUT MATERIAL: 0 Neat cement 2 Cement grout 3 Bentonite 4 Other											
Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.											
What is the nearest source of possible contamination:											
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well											
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well											
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)											
13 Insecticide storage NONE											
Direction from well? How many feet?											
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG						
0	2	Sandy top soil									
2	50	Clay, brown with finesand streaks									
50	60	Sand, med to coarse and fine gravel									
60	75	Clay, brown									
75	80	Sand, med to coarse and med gravel									
90	100	Clay, brown									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) MAY 27 81 and this record is true to the best of my knowledge and belief. Kansas											
Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) JULY 2 81											
under the business name of Central Well & Pump Inc. Pratt, Kansas by (signature) Blanton											
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.											

OFFICE USE ONLY

T

R

EW

SEC

1/4

SW

1/4

NW