

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: PRATT		SW 1/4 NW 1/4 SE 1/4	10	T 27 S	R 15 E
Distance and direction from nearest town or city street address of well if located within city? 5N 2 1/2 W OF CULLISON, KS					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		Application Number:			
City, State, ZIP Code :		Pratt, Kansas 67124			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 144 ft. ELEVATION:			
1 Mile		Depth(s) Groundwater Encountered 1. 52 ft. 2. . ft. 3. . ft.			
		WELL'S STATIC WATER LEVEL 31 ft. below land surface measured on mo/day/yr DEC 8 80			
		Pump test data: Well water was 43 ft. after 1 hours pumping 800 gpm			
		Est. Yield 1600 gpm: Well water was 49 ft. after 1 hours pumping 1200 gpm			
		Bore Hole Diameter 30 in. to 144 ft., and . in. to . ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		☒ Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes. No ☒ If yes, mo/day/yr sample was sub-			
		mitted Water Well Disinfected? Yes ☒ No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
☒ Steel 3 RMP (SR)		Welded ☒			
2 PVC 4 ABS		Threaded.			
Blank casing diameter 16 in. to 68 ft., Dia . in. to . ft., Dia . in. to . ft.					
Casing height above land surface 12 in., weight 32.7 lbs./ft. Wall thickness or gauge No. 188					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
☒ Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter ☒ Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 68 ft. to 80 ft., From . ft. to . ft.					
From 104 ft. to 144 ft., From . ft. to . ft.					
GRAVEL PACK INTERVALS: From . ft. to . ft., From . ft. to . ft.					
From 10 ft. to 144 ft., From . ft. to . ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other					
Grout Intervals: From 0 ft. to 10 ft., From . ft. to . ft., From . ft. to . ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage NONE					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Fine sandy silt			
2	7	Sand, fine			
7	20	Clay, green and sandy			
20	52	Clay, blue and green			
52	80	Sand, fine to coarse and fine to med gravel			
80	100	Clay, tan and green			
100	118	Sand, fine to coarse and coarse gravel			
118	120	Clay, green			
120	144	Sand, med to coarse and fine to very coarse gravel			
144	173	Clay, green and blue			
173	190	Shale, blue			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) FEB 3 81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) JUNE 27 81 under the business name of Central Well & Pump Inc. Pratt, Kansas by (signature) Johnonick					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					