

LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: PRATT		SE 1/4 SW 1/4 NW 1/4	28	T 27 S	R 15 E
Distance and direction from nearest town or city street address of well if located within city? 2 1/2 N 3 1/4 W OF CULLISON, KS					
WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		Application Number: 34,530			
City, State, ZIP Code :		Haviland, Kansas			
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		DEPTH OF COMPLETED WELL: 170 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 62 ft. 2. . ft. 3. . ft.			
		WELL'S STATIC WATER LEVEL 55 ft. below land surface measured on mo/day/yr Dec 11 80			
		Pump test data: Well water was 66 ft. after 1 hours pumping 800 gpm			
		Est. Yield . gpm: Well water was 70 ft. after 1 hours pumping 1200 gpm			
		Bore Hole Diameter 30 in. to 170 ft., and . in. to . ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes . No X ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued . Clamped .			
1 Steel 3 RMP (SR) 2 PVC 4 ABS		5 Wrought iron 8 Concrete tile Welded X 6 Asbestos-Cement 9 Other (specify below) Threaded .			
Blank casing diameter 16 in. to . ft., Dia . in. to . ft., Dia . in. to . ft.					
Casing height above land surface 12 in., weight 32.7 lbs./ft. Wall thickness or gauge No. 188					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 2 Louvered shutter 4 Key punched		6 Wire wrapped 9 Drilled holes			
SCREEN-PERFORATED INTERVALS:		7 Torch cut 10 Other (specify)			
From 88 ft. to 104 ft., From . ft. to . ft.					
From 126 ft. to 170 ft., From . ft. to . ft.					
GRAVEL PACK INTERVALS:		From . ft. to . ft., From . ft. to . ft.			
From 10 ft. to 170 ft., From . ft. to . ft.					
GROUT MATERIAL:		4 Other .			
1 Neat cement 2 Cement grout 3 Bentonite					
Grout Intervals: From 0 ft. to 10 ft., From . ft. to . ft., From . ft. to . ft.					
What is the nearest source of possible contamination:		15 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage NONE					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Sandy soil			
2	4	Sand, fine			
4	62	Clay, tan and brown			
62	104	Sand, fine to coarse and med gravel			
104	122	Clay, tan and gray			
122	132	Sand, fine to coarse and med gravel			
132	136	Clay, tan			
136	142	Sand, fine to coarse and med gravel			
142	150	Clay, tan			
150	170	Sand, fine to coarse and coarse gravel			
170	196	Clay, tan with caliche			
196	206	Sand, very fine to fine			
206	222	Clay, brown with sand streaks			
222	250	Sand, fine to coarse and coarse gravel			
250	260	Shale, black			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) FEB 17 81 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) JUNE 27 81					
under the business name of Central Well & Pump Inc. Pratt, Kansas by (signature) John Honnicks					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

15

E

SEC.

28

SE 1/4 SW 1/4 NE 1/4