

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction CNE NE 1/4 1/4 1/4	Section number 35	Township number T 27 S	Range number R 15 W
2. Distance and direction from nearest town or city: 2 North 1 West of Cullison Street address of well location if in city:			3. Owner of well: Lemon-McCoy-Jennings R.R. or street: Cullison, Kansas City, state, zip code: Well No. 1 (TH 2-75)			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 		6. Bore hole dia. 30" in. Completion date 1/24/76 Well depth 142 ft.	
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Sandy soil			0	2	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Sandy clay			2	10	9. Casing: Material Stl Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.91 lbs./ft. Dia. 16 in. to 106 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219	
Tan & Brown Clay			10	47	10. Screen: Manufacturer's name Doerr Metal Type Stl Dia. 16" Slot/gauze 1/8 Length 36' Set between 106 ft. and 142 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/8 to 3/16	
Clay w/some sand & gravel			47	52	11. Static water level: <input type="checkbox"/> mo./day/yr. 60 ft. below land surface Date 3/9/76	
Med. to coarse sand & gravel			52	68	12. Pumping level below land surfaces: 81 ft. after 3 hrs. pumping 800 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1000 g.p.m.	
Tan clay			68	70	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date	
Med. to coarse sand & gravel			70	94	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade	
Brown clay			94	97	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 12 ft.	
White & gray clay			97	107	16. Nearest source of possible contamination: ft. 4000 Direction West Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Fine sand - tight			107	110	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne Model number 12KM HP 30 Volts <input type="checkbox"/> Length of drop pipe 100 ft. capacity 800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Med. to coarse sand & gravel			110	142	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 1/27/76 Authorized representative	
Gray clay			142	145		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5