


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 820-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Kiowa	Fraction NW 1/4 1/4 1/4	Section number 4	Township number T 27 S R 16	Range number 16
2. Distance and direction from nearest town or city: 8 mi North 1 East of Haviland Street address of well location if in city:			3. Owner of well: Glenn Shriver R.R. or street: Coats, Kansas 67028 City, state, zip code:		
4. Locate with "X" in section below: N  Well No. 2-77 (TH 1-77)		6. Bore hole dia. 30 in. Completion date _____ Well depth 174 ft. 5-9-77			
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Sandy soil		0	2	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Fine sand		2	26	9. Casing: Material Stl Height: Above or below Threaded _____ Welded <input checked="" type="checkbox"/> Surface 12 in. RMP _____ PVC _____ Weight 34.25 lbs./ft. Dia. 16 in. to 119 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth Gauge No. .203"	
Brown clay		26	40	10. Screen: Manufacturer's name Doerr Metal Products Type Steel Dio. 16" Slot/gauze 1/8 Length 56' Set between 134 ft. and 104 ft. 134 ft. and 174 ft. Gravel pack? <input checked="" type="checkbox"/> yes Size range of material 1/8x1/2	
Med. to co. sand & gravel w/clay		40	63	11. Static water level: _____ mo./day/yr. 18 ft. below land surface Date 5-9-77	
Med. to co. sand & gravel		63	72	12. Pumping level below land surfaces: 37 ft. after 4 hrs. pumping 1002 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
Brown clay		72	89	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
Med. to co. sand & gravel		89	103	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade	
Brown clay		103	127	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.	
Med. to co. sand & gravel		127	139	16. Nearest source of possible contamination: ft 3000 Direction SW Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Brown clay		139	143	17. Pump: _____ Not installed Manufacturer's name Layne & Boulev Model number 12-KEH HP 125 Volts _____ Length of drop pipe 100 ft. capacity 1200 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Med. to co. sand & gravel		143	174	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name _____ License No. _____ Address 1011 W. Harry, Wichita, Ks. Signed [Signature] Date 5/23/77	
Brown clay		174	175	21. (Use a second sheet if needed)	
18. Elevation: Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name _____ License No. _____ Address 1011 W. Harry, Wichita, Ks. Signed [Signature] Date 5/23/77	

27
 160
 4
 1/4
 Ks.