

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: KIOWA NE 1/4 SE 1/4 NE 1/4 15 T 27 S R 17 W

Distance and direction from nearest town or city street address of well if located within city?  
 5 MILES NORTH, 3 MILES WEST, 3/4 MILE NORTH OF HAVILAND

2 WATER WELL OWNER: THOMPSON, STEVE  
 RR#, St. Address, Box #: 610 NORTH EMPORIA Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: HAVILAND, KS 67059- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 139 ELEVATION: 0																																											
<table border="1"> <tr> <td>/ \</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>1</td> <td>---</td> <td>NW</td> <td>---</td> <td>NE</td> <td>---</td> </tr> <tr> <td>M</td> <td>W</td> <td></td> <td></td> <td></td> <td>E</td> </tr> <tr> <td>i</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>l</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>e</td> <td></td> <td>SW</td> <td></td> <td>SE</td> <td></td> </tr> <tr> <td>/ \</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		/ \						1	---	NW	---	NE	---	M	W				E	i						l						e		SW		SE		/ \						Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.	
/ \																																													
1	---	NW	---	NE	---																																								
M	W				E																																								
i																																													
l																																													
e		SW		SE																																									
/ \																																													
		WELL'S STATIC WATER LEVEL 43 ft. below land surface measured on mo/day/yr 04/20/15 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm																																											
		Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm																																											
		Bore Hole Diameter 8.75 in. to 140 ft., and in. to 0 ft.																																											
		WELL WATER TO BE USED AS: LIVESTOCK																																											
		Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes																																											

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED  
 Blank casing diameter 5 in. to 120 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 23 ft. to 140 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 23 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: SEPTIC TANK  
 Direction from well? SOUTH How many feet? 2500

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	16	SILT AND SAND			
16	27	TAN CLAY			
27	78	SAND AND GRAVEL			
78	114	TAN CLAY			
114	140	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/15 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 06/04/15 under the business name of DAN HAYSE WATER WELL SERV by (signature) *Dan Hayse*