

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <i>kiowa</i>	Fraction <i>1/4 SE</i> 1/4 1/4 1/4	Section number <i>4</i>	Township number T <i>29</i> S R <i>18</i> E/W	Range number
2. Distance and direction from nearest town or city: <i>7 1/2 W 1/4 East Grensburg, Ks</i> Street address of well location if in city:			3. Owner of well: <i>Ron Ashworth</i> R.R. or street: <i>Rte 2</i> City, state, zip code: <i>Garned, Ks.</i>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <i>29</i> in. Completion date Well depth <i>168</i> ft. <i>2-21-75</i>		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Sandy Top Soil		0	4	9. Casing: Material <i>steel</i> Height: <i>Above</i> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <i>18</i> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <i>16</i> in. to <i>168</i> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <i>7</i>		
Brown & Gray Sandy Clay		4	9	10. Screen: Manufacturer's name <i>Doeris</i> Type <i>Steel</i> Dia. <i>16</i> Slot/gauge <i>3/16</i> Length <i>80</i> Set between <i>99</i> ft. and <i>99</i> ft. <i>108</i> ft. and <i>168</i> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>1/2 3/4 3/8</i>		
Fine Sand		9	11	11. Static water level: _____ mo./day/yr. <i>26</i> ft. below land surface Date <i>12-30-74</i>		
Brown & Gray Clay		11	17	12. Pumping level below land surfaces: <i>24</i> ft. after <i>14</i> hrs. pumping <i>1400</i> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <i>1600</i> g.p.m.		
Fine Sand & Sandy Clay		17	22	13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <i>1-8-75</i>		
Brown Clay		22	24	14. Well head completion: <input type="checkbox"/> Pitless adapter _____ inches above grade		
Brown & White Clay		24	29	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>10</i> ft.		
Sand & Gravel & Clay Mixed		29	40	16. Nearest source of possible contamination: ft. <i>None</i> Direction <i>W</i> Type <i>Canell</i> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
Sand & Gravel clean coarse loose		40	72	17. Pump: Manufacturer's name _____ Not installed Model number <i>2-12-MA</i> HP <i>80</i> Volts _____ Length of drop pipe <i>70</i> ft. capacity <i>700</i> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Yellow Brown & gray Clay		72	75	<div style="position: absolute; right: -100px; top: 50%; transform: translateY(-50%); font-size: 2em; font-weight: bold;"> 22 18 4 0 SE 1/4 1/4 1/4 </div>		
Sand & Gravel Clean Coarse Loose		75	96 1/2			
Brown & white Sandy clay, Sand & Gravel		96 1/2	100			
Brown & white Sandy Clay & white Rock		100	115			
Sand & Gravel Clean Coarse loose		115	149			
Brown Clay		149	151	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Rosenkrantz - Bemis 134</i> Business name _____ License No. _____ Address <i>Great Bend, Ks</i> Signed <i>Walter Radwan</i> Date <i>9/14/76</i> Authorized representative		
Sand & Gravel clean coarse loose (Use a second sheet if needed)		151	168	18. Elevation: <i>Brown & Yellow Brown Clay</i>		
19. Remarks: <i>Yellow Brown Clay</i>		168	172	Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5