


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Kiowa	Township name Valley	Fraction CSE$\frac{1}{4}$	Section number 8	Town number T27S	Range number R18W		
Distance and direction from nearest town or city: 6$\frac{1}{2}$ mi. North of Greensburg, Kansas Street address of well location if in city:				3 Owner of well: Alan Robb Address: 13100 Aix-en-Provence, FRANCE				
Locate with "X" in section below: N  W E S 1 Mile				Sketch map:				
2 Type and color of material				From	To			
				Sandy top soil		0	3	
				Yellow clay		3	11	
				Sandy clay & sand		11	27	
				Sand, gravel & clay streaks		27	40	
				Sand & gravel		40	90	
				Yellow clay & lime streaks		90	95	
				Sand & gravel		95	104	
				Pink & white clay		104	114	
				Sand & gravel		114	135	
(use a second sheet if needed)								
16 Remarks: elevation Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley				4 Well depth: 135 ft. Date of completion 4-29-75 Well diameter 24 in.				
				5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary				
				6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>				
				7 Casing: Material Steel Height: above below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. Weight 30.3 lbs./ft. 16 in. to 65 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No 16 in. to 115 ft. depth				
				8 Screen: Manufacturer W. A. Brown Type Double-slot Dia. 16" Slot gauze 1/8 Length 60' Set between 65 ft. and 105 ft. Fittings: 115' & 135' 3/8" Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material				
				9 Static water level: 30 ft. below land surface Date 4-29-75				
				10 Pumping level below land surfaces: N/C ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.				
				11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date				
				12 Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade				
				13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite Depth: From 0 ft. to 10 ft.				
				14 Nearest source of possible contamination: ft. ____ Direction ____ Type ____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes NO <input checked="" type="checkbox"/> No				
				15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name ____ Type ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed [Signature] Date 4-29-75 Authorized representative				

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5