

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 049 KIDWA : SW 1/4 SW 1/4 NW 1/4 : '10 : T 27 S : R 19 W

Distance and direction from nearest town or city street address of well if located within city?
 3 1/2 W. 8 N. OF GREENSBURG, KS

2 WATER WELL OWNER: HERRMANN, JOE 107
 RR#, St. Address, Box #: 415 PRAIRIE Board of Agriculture, Division of Water Resources
 City, State, ZIP code : KINSLEY, KS 67547- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 110 ELEVATION:
 Depth(s) Groundwater Encountered 1. 59 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 59 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 110 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 90 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 90 ft. to 110 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 110 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALL How many feet? 4

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	18	SILT & SAND			
18	39	05 SAND AND 17 GRAVEL			
39	46	TAN CLAY			
46	64	05 SAND AND 17 GRAVEL			
64	70	TAN CLAY			
70	81	05 SAND AND 17 GRAVEL			
81	91	TAN CLAY			
91	110	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/5 /91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/15/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse