

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 049 KIDWA SE 1/4 SE 1/4 SE 1/4 16 T 27 S R 19 W

Distance and direction from nearest town or city street address of well if located within city?
 4 E. 7 N. OF MULLINVILLE, KS

2 WATER WELL OWNER: BRANDT DRILLING 194
 RR#, St. Address, Box #: 107 N. MARKET, SUITE 914 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: WICHITA, KS 67202- Application Number: 920467

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 100 ELEVATION:
 Depth(s) Groundwater Encountered 1. 41 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 41 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 100 ft. and in. to ft.
 WELL WATER TO BE USED AS: OIL FIELD
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASINGS USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 80 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 80 ft. to 100 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 100 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 15 OIL/GAS WELL
 Direction from well? W. How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	4	SILT & SAND			
4	22	SANDY 17 GRAVEL			
22	32	CLAY			
32	46	05 SAND AND 17 GRAVEL			
46	61	CLAY			
61	62	05 SAND AND 17 GRAVEL			
62	75	CLAY			
75	100	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 12/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/29/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse