

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 049 KIOWA | NW 1/4 SE 1/4 SE 1/4 | 22 | T 27 S | R 19 W

Distance and direction from nearest town or city street address of well if located within city?
 4 1/2 E. & 1/2 N. OF MULLINVILLE, KS

2 WATER WELL OWNER: BRANDT DRILLING 193
 RR#, St. Address, Box #: 107 N. MARKET, SUITE 914 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: WICHITA, KS 67202- Application Number: 920465

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 100 ELEVATION:
 Depth(s) Groundwater Encountered 1. 55 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 55 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm; Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to ft. and in. to ft.
 WELL WATER TO BE USED AS: 06 OIL FIELD
 Was a chemical/bacteriological sample submitted to department? No :
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 80 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT
 SCREEN PERFORATED INTERVALS: From 80 ft. to 100 ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 100 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 15 OIL/GAS WELL
 Direction from well? W. How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	28	SANDY CLAY			
28	29	CLAY			
29	64	05 SAND AND 17 GRAVEL			
64	65	CLAY			
65	68	05 SAND AND 17 GRAVEL			
68	84	CLAY			
84	98	05 SAND AND 17 GRAVEL			
98	100	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 12/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/29/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse