

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Kiowa</b>	Fraction <b>1/4 C 1/4 NW 1/4</b>	Section number <b>34</b>	Township number T <b>27</b> S R	Range number <b>19</b> E/W
2. Distance and direction from nearest town or city: <b>2n-5w-3/4n-1/2e pf Greensburg. Ks.</b> Street address of well location if in city:			3. Owner of well: <b>Butch Pyle</b> R.R. or street: <b>106 Plaza Terrace</b> City, state, zip code: <b>Dodge City, Ka. 67801</b>		
4. Locate with "X" in section below:		Sketch map:			
		6. Bore hole dia. <u>29</u> in. Completion date _____ Well depth <u>151</u> ft. <u>4-16-77</u> 7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other 9. Casing: Material <u>Steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <u>16</u> in. to <u>151</u> ft. depth; Wall Thickness: _____ inches or Dia. _____ in. to _____ ft. depth; gage No. <u>7</u>			
5. Type and color of material		From	To		
<u>Sandy top soil</u>		0	5	10. Screen: Manufacturer's name <u>W.A. Brown</u>	
<u>Sandy brown clay</u>		5	40	Type <u>steel</u> Dia. <u>16</u> Slot/gauge <u>3/16</u> Length <u>60</u> Set between <u>90</u> ft. and <u>151</u> ft. _____ ft. and _____ ft.	
<u>Sand and gravel</u>		40	123	Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/4-3/8-1/2</u>	
<u>Brown clay</u>		123	133	11. Static water level: _____ mo./day/yr. <u>60</u> ft. below land surface Date <u>2-7-77</u>	
<u>Sand and gravel</u>		133	153	12. Pumping level below land surfaces: <u>69</u> ft. after <u>1</u> hrs. pumping <u>600</u> g.p.m. <u>73</u> ft. after <u>2</u> hrs. pumping <u>1000</u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.	
<u>Yellow brown clay</u>		153	168	13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>2-8-77</u>	
				14. Well head completion: <input type="checkbox"/> Pitless adapter _____ inches above grade	
				15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
				16. Nearest source of possible contamination: ft. <u>1 1/2</u> miles Direction <u>west</u> Type <u>septic tank</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
				17. Pump: _____ Not installed Manufacturer's name <u>W.L.B.</u> Model number <u>8-10DH</u> HP <u>80</u> Volts _____ Length of drop pipe <u>120</u> ft. capacity <u>1100</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
		(Use a second sheet if needed)			
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosencrantz-Bemis 134</b> Business name _____ License No. _____ Address <u>Great Bend, Ks. 67550</u> Signed <u>Sandy Kilgore</u> Date <u>5-18-77</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

T 22  
 R 19  
 S 34  
 Sec 34  
 1/4 C NW  
 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5