

311

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: KIOWA NE 1/4 SE 1/4 SE 1/4 34 T 27 S R 19 W

Distance and direction from nearest town or city street address of well if located within city?
 2 NORTH, 4.5 MILES WEST OF GREENSBURG

2 WATER WELL OWNER: TGT PETROLEUM CORPORTION
 RR#, St. Address, Box #: PO BOX 75097 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: WICHITA, KS 67275-0097 Application Number: 20070468

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	W	NW	NE	SE	SW	E
M						
i						
l						
e						
\						X
/						

4 DEPTH OF COMPLETED WELL 160 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 85 ft. below land surface measured on mo/day/yr 12/05/07
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 160 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: OIL FIELD

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 140 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 24 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 160 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 2 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: SEPTIC TANK
 Direction from well? EAST How many feet? 1500

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	15	SILT AND SAND			
15	18	TAN CLAY			
18	29	SAND			
29	47	TAN CLAY			
47	52	SAND AND GRAVEL			
52	56	TAN CLAY			
56	114	SAND AND GRAVEL			
114	128	TAN CLAY			
128	160	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/05/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 12/14/07 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hays