


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 NW 1/4 NE 1/4	Section number 27	Township number T 27 S	Range number R 2W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 344 Wind Rows Lake Drive Goddard, Kansas			3. Owner of well: Ron Pankratz Construction City, state, zip code: 323 Wind Rows Lake Drive Goddard, Kansas 67052		
4. Locate with "X" in section below: N 1 Mile W  E S 1 Mile			Sketch map: 6. Bore hole dia. 11 in. Completion date _____ Well depth 140 ft. 10-17-78 7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material Styrene Height: Above or below _____ Threaded _____ Welded gl Surface 12 in. RMP ☒ PVC _____ Weight _____ lbs./ft. Dia. 5 in. to 140 ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth Gauge No. .200		
5. Type and color of material			From	To	
Topsoil			0	2	
Clay			2	22	
Fine sand			22	26	
Blue shale			26	140	
					10. Screen: Manufacturer's name Sunflower plastic
					Type styrene Dia. 5"
					Slot/size .06 Length 110
					Set between 30 ft. and 140 ft.
					Gravel pack? yes Size range of material 1/2-1/8"
					11. Static water level: _____ mo./day/yr. 24 ft. below land surface Date 10-17-78
					12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
					13. Water sample submitted: _____ mo./day/yr. Yes _____ No _____ Date _____
					14. Well head completion: _____ well seal Pitless adapter 12 inches above grade
					15. Well grouted? yes 1-2 fine sand mix With: _____ Neat cement _____ Bentonite ☒ Concrete Depth: From 6 ft. to 16 ft.
					16. Nearest source of possible contamination: ft. 50 Direction East Type Sewer Well disinfected upon completion? ☒ Yes Main No
					17. Pump: _____ Not installed Manufacturer's name Jacuzzi Model number 7S4C HP 3/4 Volts 230 Length of drop pipe 80/90 ft. capacity 18 g.p.m. Type: ☒ Submersible _____ Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification:		
Topography: ____ Hill ____ Slope ____ Upland ____ Valley	Flat ground Well is to be in the basement		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name _____ License No. _____ Address Wichita, Kansas 67209 Signed m. Arnold Date 11-29-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5