



USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82g-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County: <u>Sedg.</u> Fraction: <u>NESE NW</u> Section number: <u>26</u> Township number: <u>T 27 S</u> Range number: <u>R 2 E</u>	
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>14622 1st Wichita KS</u>	
3. Owner of well: <u>Gary Ewert</u> R.R. or street: <u>5701 Redburn</u> City, state, zip code: <u>Wichita KS 67212</u>	
4. Locate with "X" in section below:  Sketch map: <u>Septic</u>  1 Mile	
5. Type and color of material	
From To	
<u>Top soil.</u> <u>0</u> <u>3</u>	
<u>Red clay.</u> <u>3</u> <u>21</u>	
<u>fine sand.</u> <u>21</u> <u>29</u>	
<u>gray clay.</u> <u>29</u> <u>30</u>	
<u>fine to med. sand.</u> <u>30</u> <u>43</u>	
<u>green shale</u> <u>43</u> <u>56</u>	
<u>Charcoal shale.</u> <u>56</u> <u>61</u>	
6. Bore hole dia. <u>1</u> in. Completion date: <u>7/18/78</u> Well depth <u>61</u> ft.	
7. <u>X</u> Cable tool <u>X</u> Rotary <u> </u> Driven <u> </u> Dug <u> </u> <u> </u> Hollow rod <u> </u> Jetted <u> </u> Bored <u> </u> Reverse rotary <u> </u>	
8. Use: <u>X</u> Domestic <u> </u> Public supply <u> </u> Industry <u> </u> <u> </u> Irrigation <u> </u> Air conditioning <u> </u> Stock <u> </u> <u> </u> Lawn <u> </u> Oil field water <u> </u> Other <u> </u>	
9. Casing: Material <u>Steel</u> Weight <u>12</u> lbs./ft. Threaded <u> </u> Welded <u>X</u> Surface <u> </u> RMP <u>X</u> PVC <u> </u> Weight <u>1.50</u> lbs./ft. Dia. <u>5</u> in. to <u>61</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>	
10. Screen: Manufacturer's name <u>sunflower</u> Type <u>200</u> Dia. <u>5</u> in. Slot/gauze <u>1/16</u> Length <u>15</u> ft. Set between <u>46</u> ft. and <u>61</u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8</u> in.	
11. Static water level: <u>19</u> ft. below land surface Date <u>7/18/78</u>	
12. Pumping level below land surfaces: <u>39</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>15-20</u> g.p.m.	
13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes <u>X</u> No Date <u> </u>	
14. Well head completion: <u>X</u> Pitless adapter <u>12</u> inches above grade	
15. Well grouted? <u>yes</u> With: <u> </u> Neat cement <u> </u> Bentonite <u>X</u> Concrete <u> </u> Depth: From <u>3</u> ft. to <u>13</u> ft.	
16. Nearest source of possible contamination: <u>100</u> ft. Direction <u>No</u> Type <u>Septic</u> Well disinfected upon completion? <u> </u> Yes <u> </u> No	
17. Pump: <u>X</u> Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: <u> </u> Submersible <u> </u> Turbine <u> </u> <u> </u> Jet <u> </u> Reciprocating <u> </u> <u> </u> Centrifugal <u> </u> Other <u> </u>	
18. Elevation:	
19. Remarks: <u>Customer to furnish 4x4x4 slab at grade around casing</u> <u>Per State Regulations</u> <u>Paul [Signature]</u>	
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Wagner Dill</u> <u>318</u> Business name <u> </u> License No. <u> </u> Address <u> </u> Signature <u> </u> Date <u>7/18/78</u> Authorized representative <u> </u>	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5