


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedgewick</u>	Fraction <u>SE 1/4 NW 1/4 NW 1/4</u>	Section number <u>24</u>	Township number <u>T 27 S</u>	Range number <u>R 2 E</u>
2. Distance and direction from nearest town or city:		3. Owner of well: <u>Mike Easter</u>				
Street address of well location in city: <u>311 Rainbow Lakes Wichita</u>		R.R. or street: <u>546 Pamela</u>				
4. Locate with "X" in section below:		City, state, zip code: <u>Wichita KS 67212</u>				
Sketch map:		6. Bore hole dia. <u>11</u> in. Completion date <u>9/28/78</u>				
		Well depth <u>65</u> ft.				
		7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary				
		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other				
		9. Casing: Material <u>Steel</u> Height: <u>12</u> in. above or below				
		Threaded ☒ Welded ☒ Surface ☐ RMP ☒ PVC ☐ Weight <u>1.50</u> lbs./ft.				
		Dia. <u>5</u> in. to <u>6.5</u> ft. depth Wall Thickness: inches or				
		Dia. <u>5</u> in. to <u>6.5</u> ft. depth Gauge No. <u>200</u>				
5. Type and color of material		From	To	10. Screen: Manufacturer's name <u>Sunflower</u>		
<u>Top soil.</u>		<u>0</u>	<u>3</u>	Type <u>209</u> Dia. <u>5</u> in.		
<u>red clay.</u>		<u>3</u>	<u>29</u>	Gauge <u>11/16</u> Length <u>8</u> ft.		
<u>fine sand.</u>		<u>29</u>	<u>38</u>	Set between <u>57</u> ft. and <u>65</u> ft.		
<u>gray clay.</u>		<u>38</u>	<u>40</u>	Gravel pack? <u>Yes</u> Size range of material <u>3/8</u>		
<u>med to coarse sand.</u>		<u>40</u>	<u>61</u>	11. Static water level: <u>33</u> ft. below land surface Date <u>9/28/78</u>		
<u>gray clay</u>		<u>61</u>	<u>65</u>	12. Pumping level below land surfaces:		
				<u>35</u> ft. after <u>1/2</u> hrs. pumping <u>10</u> g.p.m.		
				<u>35</u> ft. after <u>1</u> hrs. pumping <u>10</u> g.p.m.		
				Estimated maximum yield <u>30-40</u> g.p.m.		
				13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>9/28/78</u>		
				14. Well head completion: ☒ Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? <u>Yes</u>		
				With: <u>Neat cement</u> ☐ Bentonite ☒ Concrete		
				Depth: From <u>30</u> ft. to <u>12</u> ft.		
				16. Nearest source of possible contamination <u>100</u> ft. Direction <u>W</u> Type <u>Septic</u>		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Submersible ☐ Turbine		
				Manufacturer's name <u>Valley</u> ☐ Jet ☐ Reciprocating		
				Model number <u>1808</u> HP <u>3/4</u> Volts <u>220</u>		
				Length of drop pipe <u>40</u> ft. capacity <u>18</u> g.p.m.		
				Type: ☒ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		<u>Customer to furnish 4x4x8 ft. slab around casing at grade.</u>				
		<u>Per State Regulations</u>				
		<u>Signed X [Signature]</u>				
		20. Water well contractor's certification: <u>Wengerfully 3/8</u>				
		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.				
		Business name <u>Goldrich R</u> License No. <u>10/1/78</u>				
		Address <u>Wichita KS</u> Date <u>10/1/78</u>				
		Signed <u>[Signature]</u> Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5