


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction NW NE SE NE 1/4 SW 1/4 NE 1/4	Section number 34	Township number T 27 S R	Range number 2 WEST EE (E/W)
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: R.R. or street: City, state, zip code:			
15315 W. Esthner Wichita, Kansas			Wilbur McGee 1803 S. 151st W. Wichita, Kansas			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 11 in. Completion date _____ Well depth 70 ft. 7-22-78		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Topsoil		0	3	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight _____ lbs./ft. Dia. 5 in. to 70 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. 200		
Clay		3	10	10. Screen: Manufacturer's name _____ Sunflower Plastic Type styrene Dia. 5" Slot 1/16" Length 45' Set between 25 ft. and 70 ft. _____ ft. and _____ ft. Gravel pack? yes Size range of material 1/4-1/8"		
Fine Sand		10	20	11. Static water level: _____ mo./day/yr. 20 ft. below land surface Date 7-22-78		
Gray Shale		20	70	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.		
				13. Water sample submitted: _____ mo./day/yr. Yes ☐ No ☐ Date _____		
				14. Well head completion: ☒ Pitless adapter 12 inches above grade		
				15. Well grouted? yes 1-2 Fine Sand Mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.		
				16. Nearest source of possible contamination: ft. _____ Direction _____ Type NONE Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: _____ Not installed Manufacturer's name Sta-Rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 55 ft. capacity 20 g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		Flat Ground Septic system not installed at this time. No apparent source for contamination.		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 11-30-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5