

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Sedgwick</u> Fraction <u>SW 1/4 NW 1/4 SE 1/4</u> Section number <u>1</u> Township number <u>T 27 S</u> Range number <u>R 2 E</u>	
2. Distance and direction from nearest town or city: Street address of well location in city: <u>2446 Cedarcrest Wichita KS</u>	
3. Owner of well: <u>Odell Const.</u> R.R. or street: <u>14176 Valley Hi Rd.</u> City, state, zip code: <u>Wichita, KS 67235</u>	
4. Locate with "X" in section below: Sketch map: N W E S 1 Mile Well house Septic	
5. Type and color of material	
From To	
Top Soil. 0 2	
red clay. 2 20	
fine sand. 20 48	
blue green clay. 48 55	
med to coarse gravel. 55 69	
6. Bore hole dia. <u>5</u> in. Completion date <u>5/22/78</u> Well depth <u>69</u> ft.	
7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
9. Casing: Material <u>Steel</u> Height: <u>0</u> above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u>1.50</u> lbs./ft. Dia. <u>5</u> in. to <u>69</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>69</u> ft. depth gage No. <u>1200</u>	
10. Screen: Manufacturer's name <u>Sunflower</u> Type <u>200</u> Dia. <u>5 1/2</u> Slot gauge <u>1/16</u> Length <u>5 ft.</u> Set between <u>64</u> ft. and <u>69</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8</u>	
11. Static water level: <u>27</u> ft. below land surface Date <u>5/22/78</u> mo./day/yr.	
12. Pumping level below and surfaces: <u>28</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. <u>28</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. Estimated maximum yield <u>30</u> g.p.m.	
13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>5/22/78</u> mo./day/yr.	
14. Well head completion: ☒ Pitless adapter <u>12</u> inches above grade	
15. Well grouted? <u>Yes</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>3</u> ft. to <u>13</u> ft.	
16. Nearest source of possible contamination: <u>7.5</u> ft. Direction <u>None</u> Type <u>Septic</u> Well disinfected upon completion? ☒ Yes ☐ No	
17. Pump: <u>Not installed</u> Manufacturer's name <u>Valley</u> Model number <u>1208</u> HP <u>1/2</u> Vol <u>220</u> Length of drop pipe <u>50</u> ft. capacity <u>12</u> g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation: 19. Remarks: (Use a second sheet if needed) <u>Customer to furnish 4x4x4"</u> <u>slot around casing at grade</u> <u>per State Regulations</u> <u>Signed X Clinton E Odell</u>	
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Wminger Pilling</u> <u>3/8</u> Business name <u>Colwich</u> License No. <u>1/4 1/4</u> Address <u>Wichita, KS</u> Signed <u>Wminger Pilling</u> Date <u>5/22/78</u> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5