

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		SW ¼ SW ¼ NW ¼	12	T 27 S	R 2W E/W
Distance and direction from nearest town or city street address of well if located within city?					
1856 N. 135th West Wichita, Ks.					
2 WATER WELL OWNER: Watkins					
RR#, St. Address, Box # : 1856 N. 135th West					
City, State, ZIP Code : Wichita, Ks.					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL..... 65 ft. ELEVATION:			
N W X E S		Depth(s) Groundwater Encountered 1..... 31 ft. 2..... ft. 3..... ft.			
		WELL'S STATIC WATER LEVEL 31 ft. below land surface measured on mo/day/yr 3-21-90			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
Bore Hole Diameter 11 in. to ft., and in. to ft.					
WELL WATER TO BE USED AS:					
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)					
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well					
Was a chemical/bacteriological sample submitted to Department? Yes..... No ☒ ; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes ☒ No					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped					
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded					
Blank casing diameter 5 in. to 55 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 12 in., weight 2.29 lbs./ft. Wall thickness or gauge No.214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
SCREEN-PERFORATED INTERVALS:					
From 55 ft. to 65 ft., From ft. to ft.					
GRAVEL PACK INTERVALS:					
From 24 ft. to 65 ft., From ft. to ft.					
GROUT MATERIAL:					
1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout intervals: From 4 ft. to 24 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
Direction from well? North 13 Insecticide storage How many feet? 52					
FROM		TO		LITHOLOGIC LOG	PLUGGING INTERVALS
0		3		topsoil	
3		32		clay	
32		48		fine sand	
48		65		medium sand	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3-21-90 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 236 was completed on (mo/day/yr) 5-10-99					
under the business name of Harp Well and Pump Service, Inc. by (signature) Mary Arnold					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					