

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County SEDGWICK	Fraction 1/4 NW 1/4 NE 1/4	Section number 13	Township number T 27 S	Range number R 2W E/W	
2. Distance and direction from nearest town or city: 1317 Firefly Dr. Wichita, Kansas			3. Owner of well: R.E. Muzzy Construction			
Street address of well location if in city:			R.R. or street: 734 Butler			
			City, state, zip code: Valley Center, Kansas			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 11 in. Completion date 7-22-78		
				Well depth 65 ft. 7-22-78		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug		
				☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry		
				9. Casing: Material Styrene Height: Above or below 12 in.		
				Threaded ☐ Welded ☒ Surface 12 in.		
				RMP ☒ PVC ☐ Weight 12 lbs./ft.		
				Dia. 5 in. to 65 ft. depth Wall Thickness: inches or		
				Dia. 5 in. to 65 ft. depth gage No. 200		
5. Type and color of material			From	To	10. Screen: Manufacturer's name Sunflower Plastic	
Topsoil			0	2	Type styrene Dia. 5"	
Clay			2	14	Slot 1/4" Dia. .06 Length 15'	
Sandy Clay			14	19	Set between 50 ft. and 65 ft.	
Medium Sand with Clay Streaks			19	23	Gravel pack? yes Size range of material 1/4-1/8"	
Medium Sand			23	35	11. Static water level: 15 ft. below land surface Date 7-22-78	
Clay			35	40	12. Pumping level below land surfaces:	
Coarse Sand			40	65	____ ft. after ____ hrs. pumping ____ g.p.m.	
					____ ft. after ____ hrs. pumping ____ g.p.m.	
					Estimated maximum yield ____ g.p.m.	
					13. Water sample submitted: ____ mo./day/yr.	
					____ Yes ____ No Date ____	
					14. Well head completion:	
					☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes 1-2 Fine Sand Mix	
					With: ____ Neat cement ____ Bentonite ☒ Concrete	
					Depth: From 40" ft. to 14 ft.	
					16. Nearest source of possible contamination:	
					ft. ____ Direction ____ Type NONE	
					Well disinfected upon completion? ☒ Yes ____ No	
					17. Pump: Not installed	
					Manufacturer's name Jacuzzi	
					Model number 7S4C HP 3/4 Volts 230	
					Length of drop pipe 50 ft. capacity 20 g.p.m.	
					Type:	
					☒ Submersible ____ Turbine	
					☐ Jet ____ Reciprocating	
					☐ Centrifugal ____ Other	
					(Use a second sheet if needed)	
18. Elevation:	19. Remarks: Flat Ground		20. Water well contractor's certification:			
Topography:	Septic system not installed at this time. No apparent source for contamination.		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.			
____ Hill			Harp Well & Pump 236			
____ Slope			Business name Wichita, Kansas License No. 67209			
____ Upland			Address Wichita, Kansas			
____ Valley			Signed M. Arnold Date 9-5-78			
			Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5