

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Sedgwick</u>		Fraction <u>1/4 NE 1/4 NW 1/4</u>	Section number <u>13</u>	Township number <u>T 27 S</u>	Range number <u>R 2 E</u>																											
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1301 Firefly Wichita, Kans.</u>			3. Owner of well: <u>Pate Construction</u> R.R. or street: <u>4121 West Maple</u> City, state, zip code: <u>Wichita, Kansas</u>																													
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 6. Bore hole dia. <u>11</u> in. Completion date <u>2-2-76</u> Well depth <u>65</u> ft.																													
5. Type and color of material			7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																													
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																													
<table border="1"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td><u>Topsoil</u></td> <td><u>0</u></td> <td><u>5</u></td> </tr> <tr> <td><u>Clay</u></td> <td><u>5</u></td> <td><u>12</u></td> </tr> <tr> <td><u>fine sand</u></td> <td><u>12</u></td> <td><u>20</u></td> </tr> <tr> <td><u>medium sand (dirty & black)</u></td> <td><u>20</u></td> <td><u>35</u></td> </tr> <tr> <td><u>medium sand (clean)</u></td> <td><u>35</u></td> <td><u>47</u></td> </tr> <tr> <td><u>Clay</u></td> <td><u>47</u></td> <td><u>49</u></td> </tr> <tr> <td><u>medium sand</u></td> <td><u>49</u></td> <td><u>62</u></td> </tr> <tr> <td><u>Clay</u></td> <td><u>62</u></td> <td><u>65</u></td> </tr> </tbody> </table>				From	To	<u>Topsoil</u>	<u>0</u>	<u>5</u>	<u>Clay</u>	<u>5</u>	<u>12</u>	<u>fine sand</u>	<u>12</u>	<u>20</u>	<u>medium sand (dirty & black)</u>	<u>20</u>	<u>35</u>	<u>medium sand (clean)</u>	<u>35</u>	<u>47</u>	<u>Clay</u>	<u>47</u>	<u>49</u>	<u>medium sand</u>	<u>49</u>	<u>62</u>	<u>Clay</u>	<u>62</u>	<u>65</u>	9. Casing: Material <u>stipene</u> Height Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u> </u> lbs./ft. Dia. <u>5</u> in. to <u>65</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>		
				From	To																											
<u>Topsoil</u>	<u>0</u>	<u>5</u>																														
<u>Clay</u>	<u>5</u>	<u>12</u>																														
<u>fine sand</u>	<u>12</u>	<u>20</u>																														
<u>medium sand (dirty & black)</u>	<u>20</u>	<u>35</u>																														
<u>medium sand (clean)</u>	<u>35</u>	<u>47</u>																														
<u>Clay</u>	<u>47</u>	<u>49</u>																														
<u>medium sand</u>	<u>49</u>	<u>62</u>																														
<u>Clay</u>	<u>62</u>	<u>65</u>																														
			10. Screen: Manufacturer's name <u>Sunflower Plastic</u> Type <u>stipene</u> Dia. <u>5</u> " Slot/gauze <u>0.06</u> Length <u>20</u> ' Set between <u>45</u> ft. and <u>65</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4-1/8</u> "																													
			11. Static water level: <u>25</u> ft. below land surface Date <u>2-2-76</u> mo./day/yr.																													
			12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.																													
			13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☐ No Date <u> </u>																													
			14. Well head completion: <u>capped</u> ☐ Pitless adapter <u>12</u> inches above grade																													
			15. Well grouted? <u>yes</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>40</u> to <u>14</u> ft.																													
			16. Nearest source of possible contamination: <u>Septic Tank</u> ft. <u>75</u> Direction <u>West</u> Type <u>Septic Tank</u> Well disinfected upon completion? ☒ Yes ☐ No																													
			17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Valts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																													
18. Elevation:			19. Remarks: <u>Flat Ground</u> <u>Pump to be installed at</u> <u>a later date with a</u> <u>pitless adapter.</u>																													
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Shirley Well Pump 236</u> Business name <u>Wichita, Kans.</u> License No. <u> </u> Address <u> </u> Signed <u>M. Arnold</u> Date <u>2-4-76</u> Authorized representative																													

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5