


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

DBD

1. Location of well:		County <b>Ford</b>	Fraction <b>SE 1/4 NW 1/4 SE 1/4</b>	Section number <b>18</b>	Township number <b>T 27 S</b>	Range number <b>R 22 E</b>
2. Distance and direction from nearest town or city: <b>From Ford go 1 North, 1/2 West, 2 1/4 North, 1/4 West</b> Street address of well location if in city:				3. Owner of well: <b>Ford County Land &amp; Cattle Co.</b> R.R. or street: City, state, zip code: <b>Ford, Kansas 67842</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>28</b> in. Completion date _____ Well depth <b>356</b> ft. <b>7-31-79</b>		
		<b>SE 1/4, Sec. 18, T27S, R22W, Ford County, Kansas.</b>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Top soil				0	4	9. Casing: Material <b>Steel</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>16</b> in. to <b>156</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth Gauge No. <b>219</b>
Clay				4	18	10. Screen: Manufacturer's name <b>Doerr</b> Type <b>Louver</b> Dia. <b>16"</b> Slot/gauze <b>1/32</b> Length <b>200</b> Set between <b>156</b> ft. and <b>356</b> ft. _____ ft. and _____ ft. Gravel pack? <b>Yes</b> Size range of material <b>1.25 mm</b>
Fine to medium sand				18	30	11. Static water level: _____ mo./day/yr. <b>96</b> ft. below land surface Date <b>7-13-79</b>
Clay with sand streaks				30	78	12. Pumping level below land surfaces: <b>162</b> ft. after <b>1 1/2</b> hrs. pumping <b>1100</b> g.p.m. <b>218</b> ft. after <b>1</b> hrs. pumping <b>1920</b> g.p.m. Estimated maximum yield <b>2000</b> g.p.m.
Fine to medium sand				78	100	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____
Clay, yellow				100	150	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade
Fine to medium sand				150	164	15. Well grouted? <b>Yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Clay, yellow				164	194	16. Nearest source of possible contamination: <b>Unknown</b> ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Fine to medium sand				194	204	17. Pump: _____ Not installed Manufacturer's name <b>Worthington</b> Model number <b>12M90</b> HP <b>125</b> Volts _____ Length of drop pipe <b>320</b> ft. capacity <b>900</b> p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Black shale				204	220	18. Elevation: _____
Sandstone streaks, black shale, loose				220	280	19. Remarks:
Sandstone, loose				280	334	
Shale streaks, sandstone, medium, tight				334	356	
Black shale, tight				356	400	
(Use a second sheet if needed)						
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co., Inc.</b> <b>102</b> Business name License No. Address <b>Garden City, KS 6-846</b> Signed <b>[Signature]</b> Date <b>7-27-79</b> Authorized representative						