

306

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
COUNTY: FORD SE 1/4 SE 1/4 NW 1/4 27 T 27 S R 22 W

Distance and direction from nearest town or city street address of well if located within city?  
1.5 NORTH, 1.5 EAST, .5 NORTH, .5 EAST OF FORD

2 WATER WELL OWNER: OLIVE, RICKY  
RR#, St. Address, Box # : RR Board of Agriculture, Division of Water Resources  
City, State, ZIP code : FORD, KS 67842- Application Number:

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	W	X			E
i					
l					
e					
		SW		SE	

4 DEPTH OF COMPLETED WELL 100ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 68 ft. below land surface measured on mo/day/yr 10/10/07  
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 100 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
Blank casing diameter 5 in. to 70 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From 70 ft. to 90 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 30 ft. to 100 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
Grout Intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: SEPTIC TANK  
Direction from well? EAST How many feet? 200

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	9	SILT AND SAND			
9	68	TAN CLAY			
68	80	BROWN SANDSTONE			
80	100	GRAY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/10/07 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 12/11/07  
under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse