

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Ford	NW ¼ NW ¼ NW ¼	17	T 27 S	R 23 E(W)

Distance and direction from nearest town or city street address of well if located within city?

5 miles east of Ft. Dodge, Ks.

2 WATER WELL OWNER: Triple A Feeders	Water well permit # 37,590
RR#, St. Address, Box #: Fort Dodge Rd.	Board of Agriculture, Division of Water Resources
City, State, ZIP Code: Dodge City, Ks. 67801	Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 400 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL ... 82 ... ft. below land surface measured on mo/day/yr ... 12-22-86 ...
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield 250 gpm: Well water was ... 129 ... ft. after ... 2 ... hours pumping ... 250 ... gpm
	Bore Hole Diameter ... 15 ... in. to ... 400 ... ft., and ... in. to ... ft.
WELL WATER TO BE USED AS:	
1 Domestic ☒ Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well	
Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes ☒ No	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped
☒ Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
☒ PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter ... 8 ... in. to ... 340 ... ft., Dia. in. to ... ft., Dia. in. to ... ft.			11 Other (specify)
Casing height above land surface ... 12 ... in., weight lbs./ft. Wall thickness or gauge No. ... 250 ...			12 None used (open hole)
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	☒ Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	11 None (open hole)
		7 Torch cut	9 Drilled holes
SCREEN-PERFORATED INTERVALS: From ... 400 ... ft. to ... 380 ... ft., From ... 340 ... ft. to ... 280 ... ft.			
GRAVEL PACK INTERVALS: From ... 400 ... ft. to ... 60 ... ft., From ... ft. to ... ft.			

6 GROUT MATERIAL:	1 Neat cement	X Cement grout	X Bentonite	4 Other
Grout Intervals: From ... 0 ... ft. to ... 20 ... ft., From ... 60 ... ft. to ... 70 ... ft., From ... ft. to ... ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	X Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well?			How many feet? 100	

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	top soil			
3	23	gravel & coarse sand			
23	40	yellow shale	40	120	black shale
120	140	blue shale			
140	184	gray & red shale			
184	200	Dakota sandstone, fine, tight			
200	255	gray & red shale			
255	260	Dakota sandstone, fine, tight			
260	274	gray shale			
274	300	Dakota sandstone, fine, tight			
300	340	Dakota sandstone, med. loose			
340	388	gray & red shale			
388	400	Dakota sandstone, med. loose			
400	420	blue shale			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ... 12-22-86 ... and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. ... 449 ...	This Water Well Record was completed on (mo/day/yr) ... 12-30-86 ...
under the business name of Midwest Well & Pump	by (signature) <i>Art Kuhlman</i>

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.