

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 029 FORD SW 1/4 NW 1/4 NW 1/4 09 T 27 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 DODGE CITY, S ON 283. TO SYCAMORE ST.; 4M E, ON S SIDE

2 WATER WELL OWNER: WILROADS FEED YARD

RR#, St. Address, Box #: R.R. 3

City, State, ZIP code: DODGE CITY, KS 67801-

Board of Agriculture, Division of Water Resources

Application Number: 38162

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 178 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 80 ft. below land surface measured on mo/day/yr 07/08/96
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 11 in. to 178 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 03 FEEDLOT

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 6 in. to 178 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 118 ft. to 178 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 178 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? SOUTH How many feet? 106

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	FINE SAND			
10	30	FN-ME-CRS SAND GRAVEL			
30	62	BRWN SANDY CLAY SAND STREAKS			
62	100	FN-ME-CRS SAND BRWN CLAY STRKS			
100	160	FN-ME-CRS SAND GRAVEL			
160	189	GRAVEL SOAPSTONE BRN & TAN ROCK			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 07/10/96 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 07/16/96

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Benny Leichner