

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: FORD		NE 1/4 SW 1/4 SW 1/4	5	T 27 S	R 24 W
Distance and direction from nearest town or city street address of well if located within city? 2 MILES EAST ON WILROADS GARDEN ROAD					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: ROUTE 3		Application Number:			
City, State, ZIP code: DODGE CITY, KS 67801-					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 164 ELEVATION: 0			
<div style="border: 1px solid black; padding: 5px; text-align: center;"> </div>		Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.			
		WELL'S STATIC WATER LEVEL 51 ft. below land surface measured on mo/day/yr 10/11/95			
		Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm			
		Estimated Yield 75 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm			
		Bore Hole Diameter 9 in. to 164 ft., and in. to 0 ft.			
		WELL WATER TO BE USED AS: DOMESTIC			
		Was a chemical/bacteriological sample submitted to department? No ;			
		If yes, mo/day/yr sample was submitted Water well disinfected? Yes			
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED					
Blank casing diameter 5 in. to 164 ft., Dia in. to 0 ft., Dia in. to 0 ft.					
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21					
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC					
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT					
SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.					
GRAVEL PACK INTERVALS: From 0 ft. to 0 ft., From 0 ft. to 0 ft.					
From 40 ft. to 164 ft., From 0 ft. to 0 ft.					
From 0 ft. to 0 ft., From 0 ft. to 0 ft.					
6 GROUT MATERIAL BENTONITE					
Grout Intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.					
What is the nearest source of possible contamination: ABANDONED WELL					
Direction from well? EAST How many feet? 10					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL FINE - MED SAND CLAY			
40	60	CLAY FINE SAND IN LAYERS			
60	100	CLAY			
100	120	CLAY MED-COARSE SAND			
120	140	MED-COARSE SAND			
140	160	MED-COARSE SAND SMALL GRAVEL			
160	180	CLAY ROCK LAYERS BLUE SHALE			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/13/95 and this record is true to the best of my knowledge and belief, Kansas					
Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/31/95					
under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joel A. Crick</i>					