

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: FORD Fraction SE 1/4 SW 1/4 NW 1/4 Section Number 7 Township Number T 27 S Range Number R 24 *ELW*

Distance and direction from nearest town or city street address of well if located within city?
FROM DODGE CITY JCT 56-283 1 MILE EAST AND 1/4 MILE SOUTH

2 WATER WELL OWNER: GJERSTAD, PHIL
Ref. St. Address, Box #: 1808 BURE PARKWAY Board of Agriculture, Division of Water Resources
City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
NW	NE	SW	SE
X			

4 DEPTH OF COMPLETED WELL 120 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 80 ft. below land surface measured on mo/day/yr 05/24/96
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 5 in. to 120 ft. and in. to 0 ft.

WELL WATER TO BE USED AS: MONITORING

Was a chemical/bacteriological sample submitted to department? No :
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED
Blank casing diameter 2 in. to 120 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 24 in., weight 200 lbs/ft. Wall thickness or gauge No. 80
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 120 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 55 ft. to 120 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout intervals: From 0 ft. to 55 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: POND
Direction from well? WEST How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE SAND			
20	40	FINE - MED SAND LARGE GRAVEL			
40	60	COARSE SAND LARGE GRAVEL			
60	70	FINE - MED SAND			
70	100	FINE - MED SAND SAND ROCK LAYERS			
100	115	FINE - MED SAND ROCK			
115	120	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/yr) 05/24/96 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/07/96
under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joel C. Crick*