

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number																																																												
County: <u>Ford</u>		<u>NE 1/4 NW 1/4 SW 1/4</u>	<u>7</u>	T <u>27</u> S	R <u>24</u> <u>EW</u>																																																												
Distance and direction from nearest town or city street address of well if located within city? <u>From Ft. Dodge 2 1/2 miles - east on Hwy. 154.</u>																																																																	
2 WATER WELL OWNER: <u>Everett Steele</u>																																																																	
RR#, St. Address, Box #: <u>2007 E. La Mesa</u>				Board of Agriculture, Division of Water Resources																																																													
City, State, ZIP Code: <u>Dodge City, KS. 67801</u>				Application Number:																																																													
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>280'</u> ft. ELEVATION:																																																															
		Depth(s) Groundwater Encountered 1. _____ ft. 2. _____ ft. 3. _____ ft.																																																															
		WELL'S STATIC WATER LEVEL <u>98'</u> ft. below land surface measured on mo/day/yr <u>6-10-96</u>																																																															
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm																																																															
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm																																																															
		Bore Hole Diameter <u>9 1/2"</u> in. to <u>280'</u> ft. and _____ in. to _____ ft.																																																															
WELL WATER TO BE USED AS:																																																																	
☒ 1 Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below) ☐ 2 Irrigation ☐ 4 Industrial ☐ 7 Lawn and garden only ☐ 10 Monitoring well																																																																	
Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ ; If yes, mo/day/yr sample was submitted																																																																	
Water Well Disinfected? Yes ☒ No																																																																	
5 TYPE OF BLANK CASING USED:																																																																	
☐ 1 Steel ☐ 3 RMP (SR) ☐ 5 Wrought iron ☐ 8 Concrete tile CASING JOINTS: Glued ☒ Clamped _____ ☒ 2 PVC ☐ 4 ABS ☐ 6 Asbestos-Cement ☐ 9 Other (specify below) Welded _____ ☐ 7 Fiberglass Threaded _____																																																																	
Blank casing diameter <u>5"</u> in. to <u>300</u> ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.																																																																	
Casing height above land surface <u>12</u> in., weight _____ lbs./ft. Wall thickness or gauge No. <u>S&R 21</u>																																																																	
TYPE OF SCREEN OR PERFORATION MATERIAL:																																																																	
☐ 1 Steel ☐ 3 Stainless steel ☐ 5 Fiberglass ☒ 7 PVC ☐ 10 Asbestos-cement ☐ 2 Brass ☐ 4 Galvanized steel ☐ 6 Concrete tile ☐ 8 RMP (SR) ☐ 11 Other (specify) _____ ☐ 12 None used (open hole)																																																																	
SCREEN OR PERFORATION OPENINGS ARE:																																																																	
☐ 1 Continuous slot ☐ 3 Mill slot ☐ 5 Gauzed wrapped ☒ 8 Saw cut ☐ 11 None (open hole) ☐ 2 Louvered shutter ☐ 4 Key punched ☐ 6 Wire wrapped ☐ 9 Drilled holes ☐ 7 Torch cut ☐ 10 Other (specify) _____																																																																	
SCREEN-PERFORATED INTERVALS: From <u>200</u> ft. to <u>280</u> ft. From _____ ft. to _____ ft.																																																																	
GRAVEL PACK INTERVALS: From <u>24</u> ft. to <u>280</u> ft. From _____ ft. to _____ ft.																																																																	
6 GROUT MATERIAL: ☐ 1 Neat cement ☐ 2 Cement grout ☒ 3 Bentonite ☐ 4 Other _____																																																																	
Grout Intervals: From <u>4</u> ft. to <u>24</u> ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft.																																																																	
What is the nearest source of possible contamination:																																																																	
☐ 1 Septic tank ☐ 4 Lateral lines ☐ 7 Pit privy ☐ 10 Livestock pens ☒ 14 Abandoned water well ☐ 2 Sewer lines ☐ 5 Cess pool ☐ 8 Sewage lagoon ☐ 11 Fuel storage ☐ 15 Oil well/Gas well ☐ 3 Watertight sewer lines ☐ 6 Seepage pit ☐ 9 Feedyard ☐ 12 Fertilizer storage ☐ 16 Other (specify below) _____ ☐ 13 Insecticide storage																																																																	
Direction from well? <u>northeast</u> How many feet? <u>30'</u>																																																																	
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td><u>0</u></td> <td><u>1</u></td> <td><u>Topsoil</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>1</u></td> <td><u>20</u></td> <td><u>Brown clay</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>20</u></td> <td><u>24</u></td> <td><u>Med. sand</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>24</u></td> <td><u>180</u></td> <td><u>Shale + rock layers</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>180</u></td> <td><u>185</u></td> <td><u>Sandstone</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>185</u></td> <td><u>260</u></td> <td><u>Shale + sandstone layers</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>260</u></td> <td><u>270</u></td> <td><u>Sandstone</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>270</u></td> <td><u>280</u></td> <td><u>Shale</u></td> <td></td> <td></td> <td></td> </tr> <tr> <td><u>280</u></td> <td></td> <td><u>Sandstone</u></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	<u>0</u>	<u>1</u>	<u>Topsoil</u>				<u>1</u>	<u>20</u>	<u>Brown clay</u>				<u>20</u>	<u>24</u>	<u>Med. sand</u>				<u>24</u>	<u>180</u>	<u>Shale + rock layers</u>				<u>180</u>	<u>185</u>	<u>Sandstone</u>				<u>185</u>	<u>260</u>	<u>Shale + sandstone layers</u>				<u>260</u>	<u>270</u>	<u>Sandstone</u>				<u>270</u>	<u>280</u>	<u>Shale</u>				<u>280</u>		<u>Sandstone</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																												
<u>0</u>	<u>1</u>	<u>Topsoil</u>																																																															
<u>1</u>	<u>20</u>	<u>Brown clay</u>																																																															
<u>20</u>	<u>24</u>	<u>Med. sand</u>																																																															
<u>24</u>	<u>180</u>	<u>Shale + rock layers</u>																																																															
<u>180</u>	<u>185</u>	<u>Sandstone</u>																																																															
<u>185</u>	<u>260</u>	<u>Shale + sandstone layers</u>																																																															
<u>260</u>	<u>270</u>	<u>Sandstone</u>																																																															
<u>270</u>	<u>280</u>	<u>Shale</u>																																																															
<u>280</u>		<u>Sandstone</u>																																																															
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ (1) constructed, ☐ (2) reconstructed, or ☐ (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>6-11-96</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>533</u> This Water Well Record was completed on (mo/day/yr) <u>8-10-96</u> under the business name of <u>Jantzen Water Well Repair</u> by (signature) <u>[Signature]</u>																																																																	