

1 LOCATION OF WATER WELL: Fraction SE 1/4 SE 1/4 NW 1/4 Section Number 5 Township Number T 27 S Range Number R 24 *SW*
 COUNTY: FORD

Distance and direction from nearest town or city street address of well if located within city?
 GREEN ACRES TRAILOR COURT

2 WATER WELL OWNER: DIAZ, JAUN
 RR#, St. Address, Box #: LOT 1 -- BLOCK 3 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE
W	X	E
SW	SE	

4 DEPTH OF COMPLETED WELL 160 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 38 ft. below land surface measured on mo/day/yr 08/02/96
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 90 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 160 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 160 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 134 ft. to 154 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 160 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: SEPTIC TANK
 Direction from well? EAST How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL MED-COARSE SAND CLAY			
20	60	CLAY FINE - MED SAND			
60	80	FINE SAND			
80	100	FINE SAND COARSE SAND			
100	120	MED-COARSE SAND SMALL GRAVEL			
120	155	COARSE SAND SMALL GRAVEL LARGE			
155	180	CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/02/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/05/96
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*