

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Ford	Fraction SE 1/4 NE 1/4 SW 1/4	Section number 4	Township number T 27 S	Range number R 24 W
2. Distance and direction from nearest town or city: 1 mi East of Dodge City Street address of well location if in city:			3. Owner of well: MBPXL Corporation R.R. or street: Dodge City City, state, zip code: Kansas 67801			
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. 26 in. Completion date 4-17-80 Well depth 365 ft.	
		Well No. 4			7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
					8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
5. Type and color of material		From	To	9. Casing: Material X St Height: Above 30 in. Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 30 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 12 in. to 22 1/2 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 330		
Top soil		0	5	10. Screen: Manufacturer's name Johnson Stainless Type Wire Wrap Dia. 12" Slot/gauze 50 Length 140' Set between 225 ft. and 365 ft. Gravel pack? Yes Size range of material 1/4 x 3/8		
Med. gravel		5	25	11. Static water level: 82.8 ft. below land surface Date 4-17-80 mo./day/yr.		
White & brown clay		25	45	12. Pumping level below land surfaces: 151.9 ft. after 30 hrs. pumping 496 g.p.m. 203.6 ft. after 1 hrs. pumping 911 g.p.m. Estimated maximum yield 800 g.p.m.		
Brown clay & fine sand		45	65	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.		
Brown clay & fine sandstone		65	70	14. Well head completion: <input type="checkbox"/> Pitless adapter 30 inches above grade		
Brown clay		70	85	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 179 ft.		
Brown clay & fine sand & med. gravel		85	95	16. Nearest source of possible contamination: ft. 450 Direction South Type River Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Med. gravel & fine sand		95	140	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne Model number BRKHC HP 50 Volts 460 Length of drop pipe 220 ft. capacity 500 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Med. gravel & coarse gravel		140	150	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 4/25/80 Authorized representative		
Shale		150	185			
Shale & limestone streaks		185	220			
Med. gravel & sandstone		220	225			
Sandstone		225	245			
Sandstone w/brown and white clay strks		245	255			
Sandstone w/white & blue clay strks		255	370			
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5