

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Ford</b>	Fraction <b>SW 1/4 SW 1/4 NW 1/4</b>	Section number <b>4</b>	Township number <b>T 27 S R 24 E</b>	Range number <b>24 E</b>
2. Distance and direction from nearest town or city: <b>1 Mi. East of Dodge City</b>			3. Owner of well: <b>MBPXL Corporation</b> R.R. or street: <b>Dodge City, Kansas 67801</b> City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>36</b> in. Completion date <b>1/24/80</b> Well depth <b>149</b> ft.		
		<p style="text-align: center;">Well No. 2 (TH 5-78)</p> <p style="text-align: center; font-size: 1.5em;"><i>See Attached Map</i></p>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Top soil & fine to med. sand		0	27	9. Casing: Material <b>steel</b> Height: Above <b>concrete</b> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>120</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>70.59</b> lbs./ft. Dia. <b>18</b> in. to <b>119</b> ft. depth Wall Thickness: inches or Dia. <b>18</b> in. to <b>119</b> ft. depth gage No. <b>375</b>		
Fine sand with clay streaks		27	71	10. Screen: Manufacturer's name <b>Houston Well Screen</b> Type <b>Wire-Wrap</b> Dia. <b>18" 5/16</b> Slot/gauze <b>0.80</b> Length <b>40</b> Set between <b>109</b> ft. and <b>149</b> ft. ft. and <b>149</b> ft. Gravel pack? <b>yes</b> Size range of material <b>1/8 x 1/2</b>		
Brown clay		71	86	11. Static water level: <b>19</b> ft. below land surface Date <b>12/5/79</b>		
Fine to med. sand		86	101	12. Pumping level below land surfaces: <b>61</b> ft. after <b>4</b> hrs. pumping <b>1250</b> g.p.m. ft. after <b>4</b> hrs. pumping <b>1250</b> g.p.m. Estimated maximum yield <b>2000</b> g.p.m.		
Med. to coarse sand & gravel		101	149	13. Water sample submitted: <b>Yes</b> <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <b>12/5/79</b>		
Gray shale		149		14. Well head completion: <input type="checkbox"/> Pitless adapter <b>120</b> Inches above grade		
				15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>90</b> ft.		
				16. Nearest source of possible contamination: <b>Waste</b> ft. <b>1000</b> Direction <b>North</b> Type <b>street</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>1276</b> HP <b>75</b> Volts <b>460</b> Length of drop pipe <b>100</b> ft. capacity <b>1500</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne Western Co. 102</b> Business name <b>Wichita, Kansas</b> License No. <b>102</b> Address <b>Wichita, Kansas</b> Signed <b>[Signature]</b> Date <b>1/30/80</b> Authorized Representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5