


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Ford	SE 1/4 NW 1/4 NW 1/4	4	T 27 S	R 24 EW

Distance and direction from nearest town or city street address of well if located within city?

2 WATER WELL OWNER:	Excel Corporation	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	Fort Dodge Road, P.O. Box 1060	Application Number:
City, State, ZIP Code :	Dodge City, KS 67801	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 71' ft. ELEVATION:
--	---

	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL . . . 18' . . . ft. below land surface measured on mo/day/yr . . . 08/30/90
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield gpm: Well water was ft. after hours pumping gpm
Bore Hole Diameter: 10" . . . in. to . . . 71' . . . ft., and in. to ft.	
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 8 Air conditioning 11 Injection well	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well 12 Other (Specify below)	
Was a chemical/bacteriological sample submitted to Department? Yes No . . . X . . . If yes, mo/day/yr sample was sub-	
mitted	
Water Well Disinfected? Yes X No	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter . . . 5" . . . in. to . . . 0' - 3' . . . ft. Dia . . . 5" PVC . . . in. to . . . 3' - 51' . . . ft. Dia in. to ft.			
Casing height above land surface . . . 2' . . . in., weight lbs./ft. Wall thickness or gauge No.			

TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement		
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	6 Wire wrapped	9 Drilled holes	
2 Louvered shutter	7 Torch cut	10 Other (specify)	
3 Mill slot			
4 Key punched			

SCREEN-PERFORATED INTERVALS:	From . . . 51' . . . ft. to . . . 71' . . . ft., From ft. to ft.
	From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS:	From . . . 46' . . . ft. to . . . 71' . . . ft., From ft. to ft.
	From ft. to ft., From ft. to ft.

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From . . . 1' . . . ft. to . . . 6' . . . ft., From . . . 6' . . . ft. to . . . 46' . . . ft., From ft. to ft.				

What is the nearest source of possible contamination:	Benseal	10 Livestock pens	14 Abandoned water well	
1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	16 Other (specify below)
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage	Anaerobic Ponds

Direction from well? West How many feet? Approximately 50'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0'	4'	Top Soil			
4'	12'	Sand			
12'	18'	Sand and Large Gravel			
18'	28'	Sandy Clay			
28'	34'	Clay			
34'	42'	Sand and Gravel			
42'	47'	Brown Sandy Clay with Sand Lenses			
47'	71'	Small to Medium Sand & Gravel			
	71'	Total Depth			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) . . . 08/30/90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . . 514 This Water Well Record was completed on (mo/day/yr) . . . 09/06/90 under the business name of Miller Gearhead & Pump Repair, Inc. by (signature) <i>Ewert Miller</i>
